

170116

K. 7
2/13/84

HYDROGEOLOGIC STUDY
TECHNICAL MEMORANDUM

ECC SITE
ZIONSVILLE, INDIANA

EPA 18.5L30.0
W65230.C3

FEBRUARY 13, 1984

CONTENTS

	<u>Page</u>
INTRODUCTION	1
PROBLEM STATEMENT	1
SCOPE	3
GEOLOGIC SETTING	3
SUBSURFACE EXPLORATION PROGRAM	3
Electrical Resistivity Survey	4
Test Drilling	4
Monitoring Well Installation	4
Laboratory Soil Testing	5
SUBSURFACE CONDITIONS	7
CONCLUSIONS	14

APPENDIX A	ELECTRICAL RESISTIVITY SURVEY
APPENDIX B	BORING LOGS
APPENDIX C	MONITORING WELL CONSTRUCTION DETAILS
APPENDIX D	LABORATORY SOIL CLASSIFICATION TEST RESULTS

FIGURES

Figure

1	Monitoring Well Locations	2
2	Isometric Projection of Deep Boreholes	8
3	Isometric Projection of Shallow Boreholes	9
4	Head Difference Between Water Table and Shallow Confined Aquifer	11
5	Groundwater Contour Map	13

TABLES

Table

1	Ground Surface and Water Level Elevations	6
2	Groundwater Levels in Northside Sanitary Landfill Piezometers	12

GLT90/75

MEMORANDUM

TO: File

FROM: Dennis E. Totzke/CH2M HILL/GLO

DATE: February 13, 1984

SUBJECT: ECC Remedial Investigation
Hydrogeologic Investigation
Subtask 3-1

JOB NO: W65230.C3

INTRODUCTION


This document is a Hydrogeologic Study technical memorandum (TM) for the Environmental Chemical and Conservation Corporation (ECC) site near Zionsville, Indiana. This work was performed in partial satisfaction of Contract No. 68-01-6692, Work Assignment No. 18.5L70.0, Task 3-1 of the Remedial Investigation authorized by the U.S. EPA. The primary purpose of the TM is to provide documentation of data obtained during the drilling and installation of groundwater monitoring wells.

PROBLEM STATEMENT

Environmental Chemical and Conservation Corp. operated as a solvent processing and reclaiming facility from 1977 until May 1980. During this period, approximately 350 generators disposed of such wastes as resins, paint sludges, waste oils and flammable solvents onsite in 55-gallon drums or by bulk discharge to onsite storage tanks. Some of the solvent wastes were processed and recovered. The site was closed down in early 1982 with an outstanding waste inventory of over 25,000 drums of liquid and solid wastes, and about 300,000 gallons of bulk storage liquids.

On March 17, 1981, the Indiana State Board of Health (ISBH) sampled two wells at the ECC site: MW-2A and MW-1B (Figure 1). The analysis of the sample from the shallow well, MW-1B, indicated the presence of several organic compounds. The organic contaminants found in the sample were:

methylene chloride	5.7 mg/l
1,1-dichloroethane	950 mg/l
trichlorethylene	10 mg/l



LEGEND

● REMEDIAL INVESTIGATION MONITORING WELL
INSTALLED JUNE AND SEPTEMBER 1983.

○ NORTHSIDE SANITARY LANDFILL MONITORING
WELL OR PIEZOMETER.

X—X ECC BOUNDARY FENCE

NOTE: All well locations are approximate




FIGURE 1
MONITORING WELL LOCATIONS
ECC SITE
TM 3-1

On November 29, 1982, the ISBH sampled five groundwater monitoring wells in the vicinity of the Northside Sanitary Landfill and ECC. Organic compounds, including 1,1-dichloroethane, Trans-1,2-dichloroethylene and methyl ethyl ketone were present in four of the five samples.

SCOPE

A hydrogeologic investigation was conducted to define the soil stratigraphy, characterize aquifers and determine groundwater flow directions and gradients in the vicinity of the ECC site and to define pathways of subsurface contaminant migration. Prior to collecting any additional data, existing information was reviewed. This included a search of historical aerial photographs, domestic and industrial well logs, relevant literature, and previous soil boring and monitoring well information from the ECC site and the Northside Sanitary Landfill. A subsurface exploration program was then performed to further define conditions at the site. The program included an electrical resistivity survey, test drilling with soil sampling, rock coring and installation of monitoring wells.

GEOLOGIC SETTING

Boone County, Indiana, is in a physiographic unit known as the Tipton Till Plain, a nearly flat to gently rolling glacial plain, which is the result of continental ice sheets that covered the county about 20,000 years ago. During the period, known as the Pleistocene Epoch, large quantities of earth materials were deposited upon the bedrock surface, with a maximum thickness approaching 350 feet. The major aquifers in Boone County are in sand and gravel deposits of glacial origin. These deposits are also important sources of aggregate materials.

The bedrock formations beneath the glacial drift in Boone County consist of limestones and dolomites of Silurian and Devonian age and shales of Devonian and Mississippian age. The beds generally dip about 10 to 30 feet per mile to the southwest toward the Illinois Basin. In general, the Silurian and Devonian age formations produce small to moderate amounts of water, while the Devonian and Mississippian age shales are not usually good water producers.

SUBSURFACE EXPLORATION PROGRAM

The subsurface exploration program was conducted between May and September 1983. It involved an electrical resistivity survey performed by Gilkeson and Heigold of Champaign, Illinois, and a test drilling and monitoring well installation program performed by Mateco Drilling Co. of Grand Rapids,

Michigan, and ATEC Inc., of Indianapolis, Indiana, and directed by CH2M HILL.

ELECTRICAL RESISTIVITY SURVEY

An electrical resistivity survey was conducted to investigate the presence and lateral continuity of shallow sand and gravel deposits and the presence of fine-grained glacial tills in the vicinity of the ECC site. A secondary objective was to investigate the presence of a groundwater contaminant plume; however, baseline resistivity values were not available and measured resistivities could not be related to the presence of contaminants. The resistivity survey was useful in defining layer characteristics of geologic materials to depths greater than 100 feet. A report on the earth resistivity investigation is presented in Appendix A.

TEST DRILLING

A series of monitoring well clusters were installed around the ECC site. The wells were classified into three groups based on their relative borehole depths. Shallow boreholes (wells) were drilled to a maximum depth of about 30 feet. Intermediate boreholes (wells) were drilled to approximately 100 feet. Deep boreholes (wells) were drilled into the top of rock, approximately 155 to 165 feet. Borehole locations are shown in Figure 1. All wells were located outside of the hazardous waste site and continuous monitoring with an HNu analyzer during drilling detected no readings above background.

Boreholes were advanced through the soil using hollow-stem-augers and/or rotary drilling techniques. The drilling fluid was clear water obtained from the City of Zionsville water supply and, in some cases, bentonite mud was used to complete deep boreholes. On deep and intermediate boreholes, 6- or 4-inch diameter steel casing was used to seal off near-surface aquifers while drilling into deeper water-bearing zones. Continuous split-spoon samples were taken through the upper 20 to 30 feet in one borehole at each well cluster location to define the near-surface stratigraphy and determine the setting depth of the 6- or 4-inch temporary steel casing. Exact depths of drilling and casing are noted on the boring logs in Appendix B. Split-spoon samples were collected at 5-foot intervals below the 20- to 30-foot depth to the top of rock. One NX-size core run was advanced into rock at each deep borehole, except at borehole ECC-3C where the core barrel did not work properly.

MONITORING WELL INSTALLATION

Twelve monitoring wells were installed at seven locations around the ECC site (Figure 1). Shallow and deep wells were

installed in the boreholes at the ECC-1, 3 and 4 cluster locations. Deep, shallow and intermediate wells were installed at the ECC-2 cluster location and single shallow wells were installed at ECC-5, 6, and 7. Well construction drawings are presented in Appendix C.

Once a borehole was completed, it was cleaned of drill cuttings and fluid by flushing with City of Zionsville water. The monitoring well was then installed and developed. The development procedure at shallow wells used an air compressor to evacuate water from the standpipe above the screen. An airline was lowered down the well to a depth just above the top of the screen to ensure that no air was forced into the aquifer. The column of water in the standpipe was ejected, allowing aquifer water to surge into the well through the screen. Each well was surged until the purge water no longer contained sand or silt.

Well ECC-4A was contaminated with oil because the oil filter on the air compressor failed to work properly while developing the well. As a result, two additional wells, ECC-6A and ECC-7A, were installed along the eastern boundary of the ECC site. These two wells were developed using compressed nitrogen, rather than an air compressor, to prevent the possibility of oil contamination.

All of the deep wells and the one intermediate well were artesian, flowing at the ground surface after being completed. These were allowed to flow freely for approximately 10 to 12 hours and no other development procedure was used. The flowing wells were fitted with a special packer assembly that was lowered into the well on 1-1/4-inch PVC pipe, as shown in Appendix B. This system controls flow and allows water to be evacuated above the frost penetration zone for winter operation. Water level measurements can be taken by adding additional 1-1/4-inch diameter PVC standpipes above ground surface.

Ground surface elevations were surveyed and water levels were recorded at all wells except ECC 6A and ECC 7A on June 29, 1983. Water levels were also recorded on either July 18, 19 or 20, 1983 and September 1, 1983; that were measured with an electric sounder. Water and ground surface elevations are listed in Table 1.

LABORATORY SOIL TESTING

Laboratory testing included index tests for soil identification and classification. These consisted of Atterberg limits, moisture contents and mechanical grain size analysis. Samples were selected for testing after visual classification of all samples from a borehole and were selected on the

Table 1
GROUNDWATER ELEVATIONS
ECC SITE

<u>Well No.</u>	<u>Ground Surface Elevation Ft. - MSL</u>	<u>Top Casing Elevation Ft. - MSL</u>	<u>Feet from Ground Surface^a</u>	<u>Elevation Ft. - MSL</u>	<u>Date Recorded</u>
ECC-1A	887.13	890.13	-5.46	881.67	6/29/83
			-5.67	881.46	7/19/83
			-6.24	880.89	9/1/83
			-5.45	881.68	11/29/83
ECC-1C	886.76	889.46	+5.06	891.82	6/29/83
			+4.70	891.46	7/18/83
			+3.99	890.75	11/29/83
ECC-2A	887.21	890.21	-5.15	882.06	6/29/83
			-5.43	881.78	7/19/83
			-6.15	881.06	9/1/83
			-5.31	881.90	11/29/83
ECC-2B	886.65	889.65	+5.19	891.84	6/29/83
			+4.34	890.99	7/20/83
			+3.78	890.43	11/29/83
ECC-2C	886.80	889.70	+5.09	891.89	6/29/83
			+4.78	891.58	7/18/83
			+3.78	890.67	11/29/83
ECC-3A	876.47	878.87	-4.31	872.16	6/29/83
			-5.13	871.34	7/19/83
			-4.90	871.57	9/1/83
			-5.26	871.21	11/29/83
ECC-3C	877.19	879.59	+12.52	889.71	6/29/83
			+12.24	889.43	7/20/83
			+13.30	890.49	11/30/83
ECC-4A	884.34	887.24	-4.11	880.23	6/29/83
			-4.38	879.96	7/19/83
			-4.66	879.68	9/1/83
ECC-4C	884.54	887.24	+7.71	892.25	6/29/83
			+6.93	891.47	7/18/83
			+6.10	890.64	11/30/83
ECC-5A	887.25	889.85	-6.10	881.15	6/29/83
			-6.49	880.76	7/19/83
			-6.92	880.33	9/1/83
			-6.19	881.06	11/30/83
ECC-6A	--	--	-4.45	--	9/2/83
			-3.59	--	11/30/83
ECC-7A	--	--	-8.50 ^b	--	9/1/83
			-2.43	--	11/30/83

^aPositive sign indicates water level above ground surface; negative sign indicates water level below ground surface.

^bNoted while drilling with hollow stem augers.

GLT90/73

basis of being representative of soil types encountered. Laboratory test results are presented in Appendix D.

Mechanical grain size analysis is useful for determining the characteristics of coarse grained soils from a single borehole and for correlating stratigraphic units with similar grain size distributions from several boreholes. Grain size distributions of relatively well sorted and rounded sands and gravels can also be used to estimate soil hydraulic conductivities. Atterberg limits and moisture contents are conducted to determine the plasticity characteristics of silts and clays. This information is useful for cross borehole correlation and for making rough estimates of soil hydraulic conductivity without performing much more costly field and laboratory tests.


SUBSURFACE CONDITIONS

Soil types encountered from the ground surface to the top of rock are illustrated in Figure 2. These consist of glacial tills, glacial outwash and possibly some shallow alluvial deposits. The glacial till deposits, consisting predominantly of clayey silt and silty clay, formed the thickest sequence encountered. They appear to be highly overconsolidated based on Atterberg limits and relatively impermeable. Glacial outwash sands and gravels were found at all five boring locations. These consisted of fine to coarse sand and gravel that are highly permeable. Some alluvial deposits may occur near the ground surface, especially near the southeast corner of the ECC site and generally consist of fine sand and silty sand. A projection of shallow borings at the ECC site is shown in Figure 3. Included are some of the borings completed previously for the Northside Sanitary Landfill. The shallow soil stratigraphy appears to be very complex near the south end of the ECC site. This is probably due to the combination of till, outwash and alluvial deposits present in this area.


Three water-bearing zones occur at different elevations and appear to be fairly continuous under the site. These are:

- o A silt sand zone, approximately 5 to 15 feet below ground surface
- o A shallow sand and gravel zone, approximately 20 to 30 feet below ground surface
- o A deep sand and gravel zone, approximately 150 to 165 feet below ground surface

The water table was identified while drilling with hollow-stem augers and continuous split-spoon sampling. Depths to the water table ranged from 6 feet at ECC-3 to approximately




- LEGEND**
- ECC-1**
- BORING LOCATION
 - ▨ SILTY SAND
 - ▨ CLAYEY SILT AND SILTY CLAY WITH SOME CLAY (GLACIAL TILL)
 - ▨ SILTY SAND AND SANDY SILT WITH SOME CLAY (GLACIAL TILL)
 - ▨ LIMESTONE BEDROCK
 - ▨ SAND AND GRAVEL (GLACIAL OUTWASH)
 - ▨ SAND



NOTE: Shallow boring ECC-5 included for comparison purpose.

FIGURE 2
ISOMETRIC PROJECTION
OF DEEP BORINGS
 ECC SITE
 TM 3-1



10 feet at ECC-1, 4 and 5, to 15 feet at ECC-2. Approximate water table elevations are illustrated in Figure 4. The water table occurred in fine-grained soils, usually sandy silts or silty sands at ECC-1, 2, 4, 5, 6 and 7. At ECC-3, it occurred in a fine sand, relatively free of silt.


A shallow confined sand and gravel was identified between approximately the 20- and 30-foot depth at ECC-1, 2, 4 and 5. The potentiometric surface of this zone is at a higher elevation than the water table at these four boring locations, as shown in Figure 4. This zone appears to be a glacial outwash sand and gravel zone, which is confined by an overlying silty clay till. The confining upper till unit appears to be 10 to 15 feet thick throughout the northern half of the ECC site. This shallow confined sand and gravel was not found at ECC-3, which is within 250 feet of Finley Creek. The shallow confined zone at ECC-4 occurs at a higher elevation than at ECC-1, 2 and 5. The zone also consists of a finer, silty sand at ECC-4 than at the other boring locations. Due to the oil problem encountered when developing ECC-4A, two additional wells were added; ECC-6A and ECC-7A (Figure 1), along the unnamed ditch. An additional well was not added at the ECC-4 location because of the low permeability soils encountered there. The shallow confined zone was identified at the ECC-6 location and has very similar characteristics to the 20- to 30-foot depth at ECC-1, 2 and 5. At ECC-7, the zone is similar to ECC-4, with large amounts of silt and interbedded clay lenses. The maximum gradient in the shallow confined aquifer was found to be 0.005 between wells ECC-2A and ECC-4A.

The hydraulic conductivity was estimated, from grain size analysis, to be in the 10^{-3} to 10^{-2} cm/sec range.

Water levels measured in Northside Sanitary Landfill piezometers are listed in Table 2. Two Northside Sanitary Landfill piezometers, SB-57 and SB-60, are relatively close together, about 100 feet (Figure 3), but show a water level difference of over 7 feet as shown by the following measurements:

<u>Piezometer</u>	<u>Ground Elevation</u>	<u>Water Level Elevation</u>	
		<u>11/15/82</u>	<u>9/1/83</u>
SB-57	879.12'	880.1'	880.12'
SB-60	880.79'	872.7'	872.73'

Piezometer SB-60 appears to be monitoring the water table, while SB-57 appears to be monitoring the shallow confined aquifer. ECC-3A monitors the water table and shows water levels that correspond closely to SB-60 (Table 1). Water level contours for the water table and the shallow confined zone are shown in Figure 5.



LEGEND

 WATER ELEVATION IN SHALLOW CONFINED AQUIFER

 WATER TABLE ELEVATION NOTED WHILE DRILLING

NOTE: Shallow confined aquifer was not encountered at ECC - 3.

VERTICAL SCALE 1" = 5'


HORIZONTAL - NOT TO SCALE

FIGURE 4
HEAD DIFFERENCE BETWEEN WATER
TABLE AND SHALLOW CONFINED AQUIFER
 ECC SITE
 TM 3-1

Table 2
GROUNDWATER LEVELS IN NORTHSIDE SANITARY
LANDFILL PIEZOMETERS

Designa- tion	Ground Elevation	Groundwater Elevation		
		11/15/82 ^a	9/1/83	11/29/83
MW-1	875.88	871.4	--	--
SB-53	876.15	871.2	--	--
54	877.45	872.8	--	--
55	872.44	870.7	--	--
56	874.71	870.7	--	--
57	879.12	880.1	880.12	878.05
58	886.77	881.3	881.35	882.18
59	892.85	881.0	--	--
60	880.79	872.7	872.73	872.21
61	875.71	871.6	--	--
62	887.36	889.5	--	--
63	890.55	891.3	--	--
64	887.12	890.1	--	--
65	876.00	871.8	--	--
66	881.71	--	--	--
67	878.69	--	--	--
68	888.23	881.4	880.86	881.72
69	884.70	880.9	880.40	881.17
70	883.44	874.3	873.75	873.22
71	880.19	872.6	872.85	872.14
72	888.43	873.1	--	--
73	879.53	871.8	--	--
74	877.88	871.0	--	--
75	880.29	873.2	872.95	872.02
76	880.85	879.9	878.95	879.75
77	892.34	883.9	--	--
78	885.43	--	--	--
79	888.06	--	--	--
80	873.80	--	--	--
MW-2	877.18	875.18	--	--
MW-3	884.58	878.67	--	--
MW-4A	885.10	883.68	--	--
MW-5	886.90	882.32	--	--
MW-6	916.56	901.23	--	--
MW-7	907.83	889.83	--	--
37	888.22	884.05	884.42	886.99

^aNovember 15, 1982, water levels provided by ISBH.



LEGEND

● REMEDIAL INVESTIGATION MONITORING WELL
INSTALLED JUNE AND SEPTEMBER 1983.

○ NORTHSIDE SANITARY LANDFILL MONITORING
WELL OR PIEZOMETER.

X—X ECC BOUNDARY FENCE

CONTOURS FOR SEPTEMBER 1, 1983 DATA
880—SHALLOW CONFINED AQUIFER

872—WATER TABLE (UNCONFINED)

NOTE: Piezometer SPB-37 may not be operating
properly.




FIGURE 5
GROUNDWATER CONTOUR MAP
ECC SITE
TM 3-1

A deep confined zone was found in outwash sands and gravels near the top of rock in all four deep borings (Figure 2). The potentiometric surface of this zone is above ground surface throughout the site, as shown in Table 1. This aquifer is confined by an extensive sequence of overlying till, which consists of very stiff to hard clayey silts and silty clays with very low relative permeabilities, based on Atterberg limits and visual classification. The natural moisture contents and Atterberg limits indicate that this till is highly overconsolidated. The maximum gradient in the deep confined aquifer was found to be 0.005 between wells ECC-3C and ECC-4C. The hydraulic conductivity was estimated, from grain size analysis, to be in the 10^{-4} to 10^{-3} cm/sec range.

Several other sandy zones in the till are possibly small outwash stages and may be water-bearing zones. Monitoring well ECC-2B is completed in such a zone, approximately 100 feet below ground surface. The water level in ECC-2B is very close to the water level in the deep well, ECC-2C (Table 1). This zone is about 10 feet thick; however, other zones encountered were usually less than 5 feet thick and generally contained considerable amounts of silt and clay.

CONCLUSIONS

Two confined zones were identified in sand and gravel zones beneath the ECC site. The deep zone occurs at a depth of about 155 to 165 feet below ground surface and just above the top of rock surface. A shallow confined zone occurs at about 20 to 30 feet below ground surface. A thick glacial till sequence of hard silty clay and clayey silt separates the two. The upper zone appears to be confined by a silty clay layer. The potentiometric surface of the deep zone was found to be above ground surface at all four deep boring locations. The potentiometric surface of the shallow aquifer was above the water table at all boring locations except ECC-3, where the shallow confined zone was not encountered. Flow in both zones appears to be generally to the south, toward Finley Creek.

The water table or top of the zone of saturation in the near surface soil was identified while drilling with hollow stem augers. It occurred in fine grained soil, usually sandy silt or silty sand, except at the ECC-3 boring location, where it occurred in a clean fine sand.

Possible groundwater contaminant sources at the ECC site include the cooling water pond, the surface storage areas and spill areas around the bulk tanks. Possible pathways of contamination appear to be in the water table aquifer and along the unnamed ditch, especially near the southeast corner of the ECC site where relatively permeable soils exist near ground surface. Contaminants may also be migrating in

the shallow confined aquifer in the vicinity of the cooling water pond, which may be excavated to a depth below the top of this aquifer. Contamination of the deep confined aquifer is unlikely because of the thick sequence of low permeability soils that act as a confining layer and the very high potentiometric surface of the aquifer, which causes an upward gradient throughout the confining layer.

GLT90/54

APPENDIX A
ELECTRICAL RESISTIVITY SURVEY

AN ELECTRICAL EARTH RESISTIVITY INVESTIGATION IN THE VICINITY
OF THE ENVIRONMENTAL CONSERVATION AND CHEMICAL CORPORATION SITE

Robert H. Gilkeson and Paul C. Heigold

Introduction and Physical Setting

This report presents findings from the application of the surface electrical earth resistivity method to define shallow geologic materials in the vicinity of the Environmental Conservation and Chemical Corporation Site (ECC). The study area is shown on plate 1. The ECC Site is located adjacent to U.S. Route 421, approximately 10 miles north of the corporate boundary of Indianapolis in the eastern part of Boone County, Indiana. The physiographic setting of the area surrounding the site is the Tipton Till Plain, an extensive flat to gently rolling region formed on ground moraine till deposited during the Wisconsin glacial advance.

The ECC Site is situated immediately adjacent to a large municipal refuse landfill. An unnamed stream flows southward along the east side of the site, between the site and the covered surface of the landfill. Final cover elevations on the top of the landfill are 994 feet above sea level. Excluding the elevations on the landfill, elevations over the rest of the study area vary from approximately 906 feet in the northwestern corner to less than 869 feet along Finley Creek in the southern part.

There are drainageways along the west, south and east sides of the ECC Site. The drainageways meet near the southeast corner of the site. At a distance of 400 feet south of the junction, the combined drainage discharges into Finley Creek.

The highest elevations on the ECC Site are in a bermed area along the northwestern and northern side of the site. Elevations along the top of the berm range from 896 feet to 900 feet above sea level. Elevations on the drum storage areas within the site range from approximately 883 feet to 887 feet above sea level. Surface water from a large part of the site drains into a cooling water lagoon that is present in the east-central part of the site.

Elevations in the floor of the drainageway along the east side of the site vary from 882 feet at the northeastern corner of the site to 875 feet at the junction of the two streams in the southeastern corner of the site. Elevations in the floor of the drainageway at the northwestern corner of the site are 886 feet above sea level.

The drainageways may be zones of discharge for groundwater in short flow-paths from the site. However, a component of recharge on the site may flow southward in the shallow geologic materials to zones of discharge along Finley Creek. The composition of the shallow geologic materials is an important control on the migration of contaminants away from the site. The texture and composition of the materials affect the velocity of groundwater and the attenuation of contaminants.

Drillers records from shallow borings in the study area have established the widespread presence of sand and gravel deposits in the shallow geologic materials. The borings also established that the sand and gravel was underlain by fine-grained glacial till. Four deep borings located in the vicinity of the ECC Site that were recently drilled to the bedrock surface found thick deposits of glacial till. Inter-till deposits of sand and gravel were present in some of the borings. These sand and gravel deposits are laterally discontinuous. The total thickness of unlithified materials at the boring sites varied from 155 feet to 166 feet. A basal zone of sand and gravel (thicknesses varying from 10 to 20 feet) was present in all four borings. At three sites, the sand and gravel was in open connection with the limestone bedrock—at one site an 8 foot thick layer of glacial till separated the sand and gravel from the bedrock. Bedrock surface elevations at the sites of the four borings range from 720.5 to 724.5 feet above sea level. Monitoring wells constructed in the deep sand and gravel deposits established that artesian conditions were present. The thick deposits of glacial till and the upward groundwater gradients

in these materials are an important safeguard to prevent contamination of groundwater resources in the deep sand deposits and in the limestone bedrock.

A field investigation with the surface electrical earth resistivity method was conducted on the site to obtain information on the geologic materials. The geophysical investigation was designed to investigate the presence and lateral continuity of shallow deposits of sand and gravel and the presence of thick deposits of fine-grained glacial tills throughout the study area to depths greater than 100 feet.

Electrical Earth Resistivity Investigation

Background

The resistivity of a geologic material is a function of several variables such as matrix conduction, the size, quantity and inter-connectedness of pore spaces and the ionic strength of the contained fluid. It is obvious that the resistivity of geologic materials cannot be defined in terms of lithology alone; however, some generalizations are possible:

1. Unsaturated geologic materials have higher resistivity values than the same materials saturated.
2. Massive rocks with little pore space have high resistivities.
3. Saturated clayey sediments have low resistivities.
4. Clean sand and gravel deposits (little clay content) that are saturated with groundwater of low ionic strength will have high resistivities.
5. Geologic materials (including sand and gravel) that are saturated with groundwater of high ionic strength may have very low resistivities.

The significance of these generalizations to the geologic materials on the ECC Site are as follows:

1. Thick sand and gravel deposits should have a significantly higher resistivity than the fine-grained glacial tills.

2. The resistivity of sand and gravel deposits near the ECC Site or the landfill may be lowered if they contain contaminated groundwater of high ionic strength.
3. In some locations the surficial silty materials may be unsaturated and therefore have resistivities that are similar to values for sand and gravel.
4. The dense, massive limestone bedrock may have very high resistivity values.

Methods of Data Collection and Analysis

The geophysical field program was conducted on four separate dates—May 1, May 8, May 18, and May 22, 1983. The 52 stations where electrical earth resistivity measurements were taken are shown on plate 1. The study area contained many features that may interfere with surface electrical measurements (metal fences, metal buildings and tanks, buried and overhead electrical lines). Because of these features, a series of measurements were taken at each measurement station through a systematic expansion of the electrode array; a measurement technique known as vertical electrical sounding (VES). In the present study measurements were taken with a modified Schlumberger electrode array where a constant 10:1 ratio is maintained for the distance separating the current and potential electrodes. Apparent resistivities were calculated for all of the measurements and graphs (VES-profiles) were constructed for each station that showed the apparent resistivity values as a function of the distance of electrode separation. The graphs were then analyzed to reject erroneous values due to measurement error or interference. Representative VES-profiles for 4 stations are shown in figures 1 and 2. Current electrode spacings out to distances of 305 feet were used at most stations. At several stations measurements were made at current electrode separations of 656 feet. Appendix I presents the apparent resistivity values measured at each current electrode separation distance for the 52 stations. A digital computer program by Zohdy (1973) was




PLATE 1




FIGURE 1. VES-profiles for station no. 6 and station no. 2 on the north side of the ECC-Site. VES-6 is located 10 feet north of the metal site fence. VES-2 is located 110 feet north of VES-6 in an open field.




FIGURE 2. VES-profiles for station no. 34 and station no. 43 on the west side of the ECC-Site. VES-34 is located 25 feet west of the site fence. VES-43 is located 20 feet west of VES-34

used to solve the inversion problem to determine the layering parameters—"true" thickness and "true" resistivities of the geologic materials for each of the VES-profiles. The determined values are referred to as "true" in recognition that they are a best approximation of the real values. Figures 3 through 12 show the layering parameters for each VES station on strip records that include a lithologic interpretation. Most of the VES stations were located along 7 traverses shown on plate 1. Figures 5, 6, 8, 9, 10, 11 and 12 present geoelectric sections for each traverse.

The geophysical instruments used in the field program were a Bison Model no. 2350-B and an ABEM Terrameter Model no. SAS-300. The Terrameter instrument was used for all of the measurements on traverses B-B', C-C', D-D', E-E' and F-F'.

Results

The surface electrical earth resistivity measurements determined that the general sequence of geologic materials in the study area is a thin upper layer of low resistivity materials (interpreted to be silts and clayey silts), a middle layer of high resistivity materials (interpreted to be sand and gravel), and a thick lower layer of low resistivity materials (interpreted to be fine-grained glacial till). The middle high resistivity layer is present at all stations except for VES-12 located in the northeastern corner of the study area. The thick lower layer of low resistivity materials is present throughout the study area. Intertill deposits of sand and gravel were not detected at any of the stations. Borings have established that these deposits are present locally. These relatively thin, discontinuous deposits cannot be detected with surface electrical methods where they are interbedded in thick deposits of glacial till.

At a few stations, the electrical measurements at large electrode separation distances indicated a deep layer of high resistivity materials (the limestone bedrock).




FIGURE 3. Strip records showing layering parameters for regional stations located north of the ECC-Site.




FIGURE 4. Strip records showing layering parameters for regional stations located south of the ECC-Site.




FIGURE 5. Geoelectric section for regional stations along traverse G-G' located in the western part of the study area.




FIGURE 6. Strip records showing layering parameters for two sets of measurements taken at station no. 48. VES-48A is for a north-south alignment of electrical lines; VES-48B is an east-west alignment.




FIGURE 7. Geoelectric section for regional stations along traverse F-F' located 45 feet west of the metal fence on the west side of the ECC-Site.




FIGURE 8. Geoelectric section for stations along traverse D-D' on the western side of the ECC-Site. Stations were located 25 feet west of the site fence.




FIGURE 9. Geoelectric section for stations along traverse E-E' on the southern side of the ECC-Site.




FIGURE 10. Geoelectric section for stations along traverse C-C' on the northern side of the ECC-Site. Stations were located 10 feet north of the site fence.




FIGURE 11. Geoelectric section for stations along traverse B-B' on the eastern side of the ECC-Site. Stations were located 5-10 feet east of the site fence.




FIGURE 12. Geoelectric section for stations located east of the unnamed drainage-way on the east side of the ECC-Site near the west side of the landfill.

An example shown in figure 4 is the "true" resistivity of 1260 ohm-feet measured for geologic materials at depths greater than 140 feet at VES-52. A resistivity value of this magnitude is reasonable for the limestone bedrock. However, the available space in the study area did not allow the long current electrode separation distances necessary to accurately characterize the deeply buried limestone bedrock. Also, the very high resistivity of the limestone bedrock "masks" detection of the overlying basal sand and gravel deposits.

Table 1 compares the thickness and depth interval for the middle high resistivity layer (sand and gravel) at VES stations to the thickness of sand and gravel reported in drillers records for shallow borings at nearby locations. The approximate distance separating the VES stations and the borings is listed in the table. The layering parameters determined for the VES-profiles compare well to the drillers records, especially when the VES station and the boring are located close together.

Because of the significance of the drainageways to shallow groundwater flow systems and also because the shallow geologic materials can vary greatly over short lateral distances, it was necessary to locate VES stations between the drainageways and the metal fence that surrounds the ECC Site. The affect of the metal fence on the electrical measurements is problematic and was a reason for the decision to take all measurements with the VES method.

Table 2 presents the range in layering parameters determined for geologic materials in different parts of the study area; the values determined for the traverses in the immediate vicinity of the site and the landfill are evaluated separately from the 16 regional stations where electrical interference is less of a problem.

At the 16 regional stations, the "true" thickness of the middle layer (sand and gravel deposits) were determined to vary from 14 to 60 feet. The thickest deposits

TABLE 1

For the Vicinity of the Environmental Conservation and Chemical Corporation Site, A Comparison of the Distribution of Coarse-Grained Geologic Materials Interpreted from Vertical Electrical Soundings with Drillers Records from Shallow Borings

VES station no. or boring no. ^a	Total depth feet	Sand and gravel ^b		
		Thickness feet	Depth interval feet	Elevation interval feet
Northwest ^c				
VES-30	115	24	2-26	884-860
ECC-1C	171	9	25-34	865-856
VES-45	115	32	19-51	873-841
Western ^d				
VES-37	35	19	16-35	868-849
ECC-5A	32	15	17-32	869-854
VES-36	80	25	4-30	880-854
North ^e				
VES-7	115	36	16-52	878-842
SB-59	50.5	26	23-49	869-843
Northeast ^f				
ECC-2C	165.6	20	16-36	871-851
VES-11	55	39	12-51	879-840
VES-15	115	21	5-26	884-863
East ^g				
SB-68	30	primarily fine-grained materials, 3 feet of silty sand in the depth interval of 18-21 feet		
VES-12	80	low resistivity values—fine-grained materials		
ECC-4C	165.9	primarily fine-grained materials, few thin sand layers in the depth interval of 8-15 feet		

TABLE 1 (Continued)

VES station no. or boring no. ^a	Total depth feet	Sand and gravel ^b		
		Thickness feet	Depth interval feet	Elevation interval feet
East ^h				
VES-25	150	25	13-38	873-848
SB-79	38	24	12-36	873-849
Southeast ⁱ				
VES-14	80	32	3-35	880-848
SB-76	28.8	21.8	7-28.8	876-854
South ^j				
VES-40	50	28	2-30	878-850
SB-57	30.5	9	0-9	880-871
"	"	5	23.5-28.5	856.5-851.5
South ^k				
VES-29	80	25	3-28	876-851
SB-60	30	7	8-15	869-864
South ^l				
SB-54	30	23	0-23	873-850
VES-52	150	16	5-21	869-853
SB-55	25	23	0-23	872-849

- a. The drillers records for the borings are in Appendix II. The approximate locations of the SB-borings are shown on a figure in Appendix II.
- b. Sand and gravel present to a depth of not greater than 60 feet.
- c. Boring ECC-1C is located approximately 50 feet west of VES-30 and 175 feet east of VES-45.
- d. Boring no. ECC-5A is located along the western side of the site approximately 25 feet west of VES-37 and 60 feet south of VES-36.
- e. Boring no. SB-59 is located along the north side of the site approximately 10 feet north of VES-7.
- f. Boring no. ECC-2C is located 62 feet northeast of the northeastern corner of the site fence, approximately 100 feet northeast of VES-15 and 70 feet north-east of VES-11.
- g. Boring SB-68 is located approximately 10 feet north of VES-12; boring ECC-4C is located approximately 90 feet south of VES-12.
- h. Boring SB-79 is located within the ECC-Site on the south side of the lagoon approximately 60 feet east of VES-25.

TABLE 1 (Continued)

- i. Boring SB-76 is located approximately 20 feet south of VES-14.
- j. Boring SB-57 is located along the south side of the site approximately 10 feet north of the location of VES-40.
- k. Boring SB-60 is located along the south side of the site approximately 10 feet north of the location of VES-29.
- l. Boring SB-54 and SB-55 are located in the southern part of the study area. Boring SB-54 is located approximately 60 feet northeast of VES-52; boring SB-55 is located approximately 50 feet southwest of VES-52.

TABLE 2

The Range in Layering Parameters—"True" Thickness and "True" Resistivity for
VES-Profiles at Measurement Stations in The Study Area

	Upper layer (silts, clayey silts)		Middle layer (sand and gravel)		Lower layer (glacial till)	
	thickness feet	resistivity ohm-feet	thickness feet	resistivity ohm-feet	thickness feet	resistivity* ohm-feet
16 regional stations away from the ECC Site or landfill	2-11	72-191	14-60	213-409	~100	90-174
Stations on traverses near ECC Site						
B-B'	3-13	61-173	9-30	149-291	~100	50-142
C-C'	7-22	86-128	22-40	156-182	> 80	90-124
D-D'	0-16	65-150	19-51	182-281	> 90	77-137
E-E'	3-16	65-364	14-28	172-307	> 50	118-148
Stations near the landfill on traverse A-A'	3-5	70-120	0-39	176-294	~100	57-115

* The range does not include some anomalously low values and anomalously high values that were measured in thin layers or at the bottom of profiles.

are present in the northern and western part of the study area. The "true" resistivity of the middle layer at the 16 regional stations varied from 213 to 409 ohm-feet.

At station no. 48 on traverse G-G'; two separate sets of measurements were taken with north-south (VES-48A) and east-west (VES-48B) alignments of the electrode arrays. The layering parameters for the two VES-profiles are shown in figure 6. The layering parameters are very similar; the significant difference is a greater thickness of the middle layer for VES-48A.

The VES-profiles in figure 1 and 2 illustrate the lower apparent resistivity values that were measured at stations located near the metal fence surrounding the ECC Site. The shape of all 4 curves is characteristic of the 3-layer case where the middle layer has higher resistivity, but the apparent resistivity values are systematically lowered for the stations that are located near the metal fence. The range of values listed in Table 2 demonstrate that the "true" resistivity values for the middle layer are lower for stations near the ECC Site than for the regional values. The lowest values were for stations located along traverse C-C' on the north side of the site between the metal fence and a woven wire farm fence. The ground surface and fences were wet from a rain storm when measurements were taken along this traverse. The systematic lowering of the "true" resistivity values for the middle layer is also evident when the strip records in figures 7 and 8 for stations along traverse F-F' and D-D' are compared. The stations on traverse F-F' are located 20 feet west of traverse D-D' on the west side of the drainageway.

An important control on the resistivity of sand and gravel deposits is the ionic strength of the contained groundwater. Therefore, water quality data from monitoring wells in the vicinity of the ECC Site were acquired from the Indiana Department of Public Health to investigate the possibility that the lower resistivities near the ECC Site were due to the presence of contaminants that had increased

the ionic strength of the shallow groundwater. Analyses for chloride, total dissolved solids and specific conductance are tabulated for groundwater samples from 9 shallow monitoring wells in the study area on a map in Appendix III.

The values for chloride, total dissolved solids, and specific conductance for groundwater from 2 wells located north of the site (no. 58 and no. 59) and 1 well on the site (no. 57 located south of the lagoon) are very similar to values for those constituents in monitoring well no. 37 located in the grass field west of the site. Specific conductance varies from 560 to 620 μ siemens/cm for the 3 wells in the vicinity of the site compared to a value of 605 μ siemens/cm for groundwater from well no. 37. Higher values for chloride, total dissolved solids and specific conductance were measured in 2 wells located immediately south of the ECC Site. For specific conductance the values range from 585-670 μ siemens/cm at well no. 57 and from 1060 to 1230 μ siemens/cm at well no. 60. Note that the highest concentration for the three constituents were measured in shallow monitoring wells located in the southern part of the study area. Specific conductances of 1300 and 1500 μ siemens/cm were measured at well no. 56 and no. 55 respectively.

The increase in ionic strength in groundwater south of the site is sufficient to cause a decrease in the resistivity values measured for the sand and gravel deposits. However, the decrease that has occurred is not evident in the "true" resistivity values at either station no. 29 that is located near monitoring well no. 60 or at station no. 52 that is located in the vicinity of monitoring wells no. 55 and no. 56. The decline in resistivity that has occurred cannot be evaluated without values for baseline resistivities before the contamination occurred.

It is highly probable that electrical interference by the metal fences is the major reason for the lower resistivity values at stations near the ECC Site. Although the "true" resistivity of the middle layer is lowered at these stations,

the depth interval of the layer correlates well with sand and gravel deposits reported in drillers records for nearby borings. Examples listed in Table 1 are VES-37 and ECC-5A on the western side, VES-7 and SB-59 on the north side, VES-25 and SB-79 on the east side, VES-40 and SB-57 on the south side and VES-29 and SB-60 at the southeast corner of the site. The data indicate that sand and gravel deposits are present at a shallow depth throughout the vicinity of the ECC Site; at depth the sand and gravel deposits are underlain by thick deposits of glacial till. The "true" thickness of the sand and gravel deposits ranges from 10 to 50 feet. The thickest deposits were present at stations located on the north, east and southeast sides of the site.

The shallow sand and gravel deposits are absent in a locality that is directly east of the northeastern part of the ECC Site on the eastern side of the unnamed drainageway. The low "true" resistivity values determined at VES-12 shown on traverse A-A' in figure 12 indicate that the geologic materials to a depth of at least 80 feet are primarily fine-grained. This interpretation is supported by the drillers records for two borings (SB-68 and ECC-4C) that are located in the same locality. The data indicate that in this locality the sand and gravel deposits terminate a short distance east of the ECC Site approximately along a line that is marked by the drainageway. The southern distance to which the sand and gravel deposits are absent on the east side of the drainageway is not well-defined. The layering parameters determined for stations VES-13 and VES-14 indicate that the middle layer (sand and gravel deposits) is present in the southern part of traverse A-A'. This interpretation is supported by the drillers records at boring SB-76. VES-13 is located approximately 110 feet south of boring ECC-4C.

Conclusions

A surface electrical earth resistivity investigation in the vicinity of the ECC Site identified 3 layers in the unlithified geologic materials present to depths of greater than 100 feet—1) an upper layer of low resistivity materials interpreted to be silts and clayey silts, 2) a middle layer of high resistivity materials interpreted to be sand and gravel, and 3) a thick layer of low resistivity materials interpreted to be fine-grained glacial till. The lower layer is present throughout the entire study area. The middle layer (sand and gravel) occurs over most of the study area and is only known to be absent in a small locality in the northeastern part. Thickness of the sand and gravel is interpreted to vary from 0 to approximately 60 feet. The thickest deposits are present in the northern and western parts of the study area. The resistivity values indicate that the sand and gravel deposits are present throughout the vicinity of the ECC Site.

Because of the absence of baseline values, the resistivities measured in the study cannot be related to the presence of contaminants in the shallow groundwater. Electrical interference by the metal fence is believed to be the major reason for the lower resistivity values measured for the middle layer in the immediate vicinity of the ECC Site. A significant aspect of the field study was the finding that the layering parameters of geologic materials to depths of greater than 100 feet can be determined from vertical electrical sounding measurements taken at stations that are located within 5 to 10 feet of metal fences.

References

- Zohdy, A.A.R., 1973. A Computer Program for the Automatic Interpretation of Schlumberger Sounding Curves Over Horizontally Stratified Media. National Technical Information Service, U.S. Dept. of Commerce PB-232703, 32 p.

Plate 1. The Study Area for the Surface Electrical Earth Resistivity Investigation in the Vicinity of the ECC-Site. The Map Shows the Locations of VES Stations and the Traverse Lines for Geoelectrical Sections.

APPENDIX 1

Apparent Resistivities* For Vertical Electrical Sounding Profiles At Stations Located On The Environmental Conservation And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.**					
	1	2	3	4	5	6
	apparent resistivity (ohm-feet)					
6.6	92.20	75.47	114.76	192.14	120.13	96.43
9.6	101.84	81.93	115.06	203.09	113.61	99.61
14.2	139.89	102.46	128.57	167.18	113.22	102.79
20.7	165.08	112.40	147.99	161.17	116.86	111.48
30.4	178.56	134.11	161.60	164.75	124.90	120.17
44.6	195.75	158.71	179.61	172.10	134.74	126.41
65.6	215.92	189.94	205.45	190.69	145.79	132.02
96.4	223.95	210.83	216.90	213.23	141.66	125.98
141.4	227.33	211.59	222.44	209.85	137.49	119.91
207.4	225.20	223.56	201.22	208.21	122.18	105.51
304.6	222.28		227.14	188.00		91.08
447.0						116.34
656.0						98.38

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

**The locations of the stations are shown on the base map.

APPENDIX I (Con't)

Apparent Resistivities For Vertical Electrical Sounding Profiles At Stations Located On The Environmental Conservation And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	7	8	9	10	11	12
	apparent resistivity (ohm-feet)					
6.6	104.99	82.26	118.24	119.78	125.91	85.21
9.6	108.86	97.97	113.25	131.95	134.48	90.29
14.2	113.42	100.04	109.74	128.47	142.77	87.77
20.7	114.27	101.71	106.20	124.44	151.04	99.31
30.4	116.41	112.60	115.91	131.29	153.14	88.88
44.6	119.81	126.05	121.55	134.48	155.24	92.33
65.6	125.39	135.59	133.56	137.62	154.68	87.67
96.4	135.39	139.49	137.33	147.66	154.09	114.34
141.4	142.74	139.03	133.66	146.22	148.02	69.99
207.4	130.08	132.18		144.74		48.74
304.6	126.80	115.91				
447.0						
656.0						

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Apparent Resistivities* For Vertical Electrical Sounding Profiles At Stations Located On The Environmental Conservation And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	13	14	15	16	17	18
	apparent resistivity (ohm-feet)					
6.6	111.61	72.48	118.34	131.98	116.73	196.20
9.6	117.32	75.99	117.55	140.54	108.60	161.50
14.2	120.63	91.61	114.76	138.15	118.04	144.94
20.7	123.95	106.76	118.80	139.36	118.30	128.34
30.4	146.55	135.98	136.02	143.92	118.53	125.82
44.6	156.48	159.24	142.38	155.37	120.14	129.88
65.6	166.39	183.45	147.30	162.36	131.00	125.00
96.4	166.75	178.69	138.21	156.02	126.41	125.06
141.4	148.84	139.89	129.13	141.63	115.88	108.40
207.4	130.90		129.03	120.63		82.13
304.6	129.06		128.93			71.56
447.0	127.19		122.08			
656.0	105.51		115.19			

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Apparent Resistivities* For Vertical Electrical Sounding Profiles At Stations Located On The Environmental Conservation And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	19	20	21	22	23	24
	apparent resistivity (ohm-feet)					
6.6	128.96	153.89	96.49	109.58	92.29	106.00
9.6	119.16	144.71	109.12	117.39	107.55	110.10
14.2	116.07	130.97	122.67	125.19	121.91	120.47
20.7	119.75	132.54	136.18	136.90	136.28	128.31
30.4	129.16	134.11	144.32	148.58	150.68	138.41
44.6	142.02	145.79	152.45	164.62	160.35	151.14
65.6	113.84	157.47	153.43	161.08	163.14	149.86
96.4	85.64	150.09	137.56	145.27	142.94	142.64
141.4	74.78	134.64	117.62	105.18	120.67	113.32
207.4		118.17	93.31	84.78	89.83	89.60
304.6		101.71		86.16	79.11	
447.0				87.51	88.46	
656.0				82.82	64.94	

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Apparent Resistivities* For Vertical Electrical Sounding Profiles At Stations Located On The Environmental Conservation And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	25	26	27	28	29	30
	apparent resistivity (ohm-feet)					
6.6	161.54	84.82	184.00	177.28	97.41	119.22
9.6	153.53	103.15	167.28	156.98	103.64	130.18
14.2	145.50	113.88	150.55	143.92	107.71	151.60
20.7	140.64	120.11	158.55	147.07	137.30	184.04
30.4	146.35	126.34	166.52	154.45	151.07	205.68
44.6	152.06	146.55	180.26	165.90	166.46	204.60
65.6	159.90	148.35	194.01	171.28	181.84	203.75
96.4	164.39	148.25	182.23	164.39	172.23	194.17
141.4	141.63	121.68	160.88	141.63	162.62	193.02
207.4	125.46	92.03	123.78	112.89	135.26	148.87
304.6	109.25	71.20	86.65			139.40
447.0	105.05					210.14
656.0						212.38

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Apparent Resistivities* For Vertical Electrical Sounding Profiles At Stations Located On The Environmental Conservation And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	31	32	33	34	35	36
	apparent resistivity (ohm-feet)					
6.6	188.56	89.77	95.12	115.65	97.87	72.35
9.6	189.45	95.08	108.76	118.60	121.03	91.24
14.2	190.30	100.56	114.17	121.52	140.97	112.97
20.7	201.22	116.83	121.39	133.20	160.91	144.51
30.4	200.44	142.41	138.25	147.30	178.46	171.74
44.6	207.68	159.24	162.03	171.41	180.92	182.49
65.6	199.68	172.10	177.77	183.45	183.45	189.94
96.4	188.20	167.96	179.87	188.20	171.54	176.30
141.4	174.88	152.12	166.13	167.87	153.89	150.38
207.4	156.32	123.19	134.18	130.90	128.34	125.75
304.6	143.17	101.71	107.71	101.71	109.25	
447.0	188.01	132.71	143.76			
656.0	178.60					

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Apparent Resistivities* For Vertical Electrical Sounding
Profiles At Stations Located On The Environmental Conservation
And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	37	38	39	40	41	42
	apparent resistivity (ohm-feet)					
6.6	140.22	302.77	502.66	98.95	116.73	135.59
9.6	143.40	251.34	310.41	125.91	129.26	133.43
14.2	145.66	168.75	233.79	128.18	137.69	134.84
20.7	150.25	129.85	161.90	139.36	146.51	144.09
30.4	154.84	137.13	171.41	155.96	165.83	162.06
44.6	160.35	152.06	194.66	172.33	189.97	188.23
65.6	161.54	166.39	210.24	168.03	212.05	217.16
96.4	167.96	160.81	182.23	160.81	216.18	218.41
141.4				155.63	203.39	205.91
207.4					180.53	175.84
304.6					153.76	145.96
447.0					199.68	
656.0					186.17	

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Apparent Resistivities* For Vertical Electrical Sounding
Profiles At Stations Located On The Environmental Conservation
And Chemical Corporation Site

Current electrode separation distance (feet)	Vertical electrical sounding station no.				
	43	44	45	46	47
	apparent resistivity (ohm-feet)				
6.6	95.84	71.01	107.22	114.93	140.18
9.6	106.20	76.12	122.08	122.67	152.45
14.2	126.60	109.81	151.79	126.47	164.72
20.7	150.38	125.55	157.07	147.50	175.54
30.4	174.59	156.16	177.38	160.94	186.20
44.6	190.30	186.82	197.42	184.13	196.86
65.6	211.56	220.74	210.24	209.19	208.60
96.4	207.19	231.89	225.86	227.89	216.80
141.4	192.73	218.21	228.38	216.84	225.59
207.4	172.79	181.64	227.40	193.02	213.03
304.6	136.02	151.47	216.77	—	192.14
447.0			254.40	287.30	205.65
656.0					219.16

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).

APPENDIX I (Con't)

Current electrode separation distance (feet)	Vertical electrical sounding station no.					
	48A	48B	49	50	51	52
	apparent resistivity (ohm-feet)					
6.6	150.15	142.88	89.28	139.66	254.88	125.91
9.6	146.51	138.19	77.90	128.05	202.50	159.34
14.2	152.12	154.23	89.70	135.95	174.88	167.34
20.7	159.14	162.23	108.83	157.63	169.41	196.34
30.4	192.14	188.73	131.46	179.54	181.22	216.48
44.6	206.83	201.29	159.80	201.42	210.14	230.58
65.6	226.48	220.81	189.94	226.35	237.04	241.63
96.4	228.71	228.71	210.83	234.12	229.89	237.14
141.4	220.35	215.10	218.61	218.87	215.10	227.33
207.4	207.91	201.49	189.94	203.58	205.85	214.38
304.6	202.70	188.37				234.45
447.0	170.36					291.72
656.0	137.99					

*Apparent resistivities in ohm-feet as a function of the distance separating the current electrodes in feet (Schlumberger Electrode Array).


APPENDIX II

Drillers Records for Borings in the Vicinity of the ECC-Site

The location map and the records for the SB-borings are from records on file at the Indiana Department of Public Health.

The drillers records for the ECC-borings were provided by the Milwaukee Office of CH2MHILL.

FIGURE 7 BORING LOCATIONS
WESTERN PORTION



ATEC Associates, Inc.



Consulting Geotechnical & Materials Engineers

LOG OF BORING NO. SB-54

CLIENT Northside Sanitary Landfill

JOB NO. 21-21043

PROJECT NAME Water Survey

START DATE 8-9-82

PROJECT LOCATION Zionsville, Indiana

FINISH DATE 8-9-82

BORING LOCATION _____

BORING METHOD HSA

FOREMAN J. Heffelmire

ROCK CORE DIA. _____ IN

INSPECTOR _____

SHELBY TUBE DIA. _____ IN

SOIL/ROCK DESCRIPTION		STRATUM DEPTH, FT.	DEPTH, FT.	STD. PENETRATION			SHELBY TUBE NO.	BORING AND SAMPLING NOTES
SURFACE ELEVATION	DATUM			SAMPLE NO.	BLOWS/6 IN. THREE 6 IN. INCREMENTS	RECOVERY, %		
Brown wet SAND and GRAVEL		23.5	23.0	1	1 2/3	75		
				2	6 11/11	100		
				3	15 18/25	100		
				4	18 27/34	100		
Gray moist HARDPAN		23.5	25.0	5	37 43/47	100		
				6	27 54/92	100		
Bottom test boring @ 30.0'			30.0					

WATER LEVEL OBSERVATIONS

NOTED ON RODS 6.0 FT.

AT COMPLETION _____ FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
CFA - CONTINUOUS FLIGHT AUGER
DC - DRIVEN CASING
MD - MUD DRILLING
RC - ROCK CORING

* THESE SHELBY TUBE
SAMPLES OBTAINED IN
AN AUXILIARY BORING
DRILLED A FEW FEET
FROM THIS BORING

CLIENT Northside Sanitary Landfill

JOB NO. 21-21043

PROJECT NAME Water Survey

START DATE 8-10-82

PROJECT LOCATION Zionsville, Indiana

FINISH DATE 8-10-82

BORING LOCATION _____

FOREMAN J. Heffelmire

BORING METHOD HSA

INSPECTOR _____

ROCK CORE DIA. _____ IN

SHELBY TUBE DIA. _____ IN

SOIL/ROCK DESCRIPTION		STRATUM DEPTH, FT.	DEPTH, FT.	STD. PENETRATION			SHELBY TUBE NO.	BORING AND SAMPLING NOTES
SURFACE ELEVATION	DATUM			SAMPLE NO.	BLOWS/6 IN. THREE 6 IN. INCREMENTS	RECOVERY, %		
Black wet SAND Organics				1	3 6/8	75		
		9.7		2	7 1/6	100		
Gray wet SAND		13.5		3	34 16/15	75		
Gray wet SAND and GRAVEL ¹				4	16 15/45	25		
		23.5		5	67.6 ⁹⁰			
Brown and gray moist weathered HARDPAN			25					Cobble at 20.0' hard drilling after cobble
Bottom test boring @ 25.0'								3" spoon DEC 23

WATER LEVEL OBSERVATIONS

NOTED ON RODS 7.5 FT.

AT COMPLETION _____ FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
CFA - CONTINUOUS FLIGHT AUGER
DC - DRIVEN CASING
MD - MUD DRILLING
PC - ROCK CORING

*THESE SHELBY TUBE
SAMPLES OBTAINED IN
AN AUXILIARY BORING
DRILLED A FEW FEET
FROM THIS BORING



LOG OF BORING NO. SB-57

JAN 31 4 49 PM '83

CLIENT Northside Sanitary Landfill DIV. OF LAND POLLUTION CONTROL
 PROJECT NAME Water Survey STATE DEPT. OF HEALTH
 PROJECT LOCATION Zionsville, Indiana
 BORING LOCATION _____
 FOREMAN J. Heffelmire
 INSPECTOR _____

JOB NO. 21-21043
 START DATE 8-10-82
 FINISH DATE 8-10-82
 BORING METHOD HSA
 ROCK CORE DIA. _____ IN.
 SHELBY TUBE DIA. _____ IN.

SOIL/ROCK DESCRIPTION	STRATUM DEPTH, FT.	DEPTH, FT.	SAMPLE NO.	STD. PENETRATION			SHELBY TUBE NO.	BORING AND SAMPLING NOTES
				BLOWS/8 IN. THREE 8 IN. INCREMENTS	RECOVERY, %			
SURFACE ELEVATION _____ DATUM _____								
Brown and gray SILTY SAND			1	3 3/5	75			
		5						
		8.5						
Gray moist SILTY CLAY with Gravel		10	2	7 8/9	100			
		15	3	4 5/8	100			
Wet gray SAND and GRAVEL Wet gray SILTY CLAY		18.5						
		19.0	4	5 4/3	80			
		20						
Gray wet SAND and GRAVEL		23.5						
		25	5	10 9/16	100			
		28.5						
Gray HARDPAN		30	6	28 45/65	75			
			7					
		35						
		40						

WATER LEVEL OBSERVATIONS

NOTED ON RODS 14.0 FT.
 AT COMPLETION _____ FT.
 AFTER _____ MRS. _____ FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
 CFA - CONTINUOUS FLIGHT AUGER
 DC - DRIVEN CASING
 MD - MUD DRILLING
 RC - ROCK CORING
 CA - CASING ADVANCER

*THESE SHELBY TUBE SAMPLES OBTAINED IN AN AUXILIARY BORING DRILLED A FEW FEET FROM THIS BORING

Geotechnical Lab
 24-10-82

CLIENT Northside Sanitary Landfill

JOB NO. 21-21043

PROJECT NAME Water Survey

START DATE 8-12-82

PROJECT LOCATION Zionsville, Indiana

FINISH DATE 8-12-82

BORING LOCATION _____

FOREMAN J. Heffelmire

STD. PENETRATION

BORING METHOD HSA

INSPECTOR _____

ROCK CORE DIA. _____ IN

SHELBY TUBE DIA. _____ IN

SOIL/ROCK DESCRIPTION		STRATUM DEPTH, FT.	DEPTH, FT.	SAMPLE NO.	BLOWS/6 IN. THREE 6 IN. INCREMENTS	RECOVERY, %	SHELBY TUBE NO.	BORING AND SAMPLING NOTES
SURFACE ELEVATION	DATUM							
Brown moist SILTY SAND with trace of Clay		8.5	5	1	2 6/8	50		
Brown moist SILTY SANDY CLAY with Gravel		23.5	10	2	9 16/19	100		
			15	3	6 9/13	100		
			20			90	1	
Gray wet SAND and GRAVEL		38.5		4	2 4/6	20		
				5	15 21/26	100		
				6	15 19/26	100		
Gray wet SAND				7	16 22/29	100		

WATER LEVEL OBSERVATIONS

NOTED ON RODS 17.5 FT.

AT COMPLETION _____ FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
CFA - CONTINUOUS FLIGHT AUGER
DC - DRIVEN CASING
MD - MUD DRILLING

* THESE SHELBY TUBE
SAMPLES OBTAINED IN
AN AUXILIARY BORING
DRILLED A FEW FEET
FROM THIS BORING

CLIENT Northside Sanitary Landfill
 PROJECT NAME Water Survey
 PROJECT LOCATION Zionsville, Indiana
 BORING LOCATION _____
 FOREMAN J. Heffelmire
 INSPECTOR _____

JOB NO. 21-21043
 START DATE 8-12-82
 FINISH DATE 8-12-82
 BORING METHOD HSA
 ROCK CORE DIA. _____ IN.
 SHELBY TUBE DIA. _____ IN.

SOIL/ROCK DESCRIPTION		STRATUM DEPTH, FT.	DEPTH, FT.	STD. PENETRATION			SHELBY TUBE NO.	BORING AND SAMPLING NOTES
SURFACE ELEVATION	DATUM			SAMPLE NO.	BLOWS/6 IN. THREE 6 IN. INCREMENTS	RECOVERY, %		
Gray wet fine SAND		48.5		8	20 15/30	30		Very hard drilling @ 45.5'
				9	40/50 0.4	100		
Gray moist HARDPAN			50					3" spoon below 49.5' to 50.5'
Bottom test boring @ 50.5'								

WATER LEVEL OBSERVATIONS

NOTED ON RODS 17.5 FT.
 AT COMPLETION _____ FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
 CFA - CONTINUOUS FLIGHT AUGER
 DC - DRIVEN CASING
 MD - MUD DRILLING
 RC - ROCK CORING

* THESE SHELBY TUBE
 SAMPLES OBTAINED IN
 AN AUXILIARY BORING
 DRILLED A FEW FEET
 FROM THIS BORING

ATEC Associates, Inc.



Consulting Geotechnical & Materials Engineers

LOG OF BORING NO. SB-60

CLIENT Northside Sanitary Landfill

JOB NO. 21-21043

PROJECT NAME Water Survey

START DATE 8-12-82

PROJECT LOCATION Zionsville, Indiana

FINISH DATE 8-13-82

BORING LOCATION _____

FOREMAN J. Heffelmire

INSPECTOR _____

STD. PENETRATION

BORING METHOD HSA

ROCK CORE DIA. _____ IN.

SHELBY TUBE DIA. _____ IN.

SOIL/ROCK DESCRIPTION	STRATUM DEPTH, FT.	DEPTH, FT.	SAMPLE NO.	BLOWS/6 IN. THREE 6 IN. INCREMENTS	RECOVERY, %	SHELBY TUBE NO.	BORING AND SAMPLING NOTES
SURFACE ELEVATION _____ DATUM _____							
Dark gray moist SANDY SILT with trace of Clay					90	1	
	8.5	5					
Gray wet SILTY SAND and GRAVEL		10	1	11 11/11	20		
	13.5						
Brown wet CLAYEY SAND and GRAVEL	14.0		2	13	100		
Gray wet fine SAND	14.5	15		38/48			
Gray moist HARDPAN							
		20	3	20 33/57	100		
		25	4	50 0.5			
		30	5	50 0.3			
Bottom test boring @ 30.0'							

Twist off @17.0'
back 3.0' redrill

WATER LEVEL OBSERVATIONS

NOTED ON RODS none FT.

AT COMPLETION 5.0 FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
CFA - CONTINUOUS FLIGHT AUGER
DC - DRIVEN CASING
MD - MUD DRILLING
RC - ROCK CORING

*THESE SHELBY TUBE
SAMPLES OBTAINED IN
AN AUXILIARY BORING
DRILLED A FEW FEET
FROM THIS BORING



CLIENT	Northside Sanitary Landfill				JOB NO.	21-21058
PROJECT NAME	Landfill				START DATE	10-22-82
PROJECT LOCATION	Zionsville, Indiana				FINISH DATE	10-22-82
BORING LOCATION					BORING METHOD	HSA
FOREMAN	E. Lomax				ROCK CORE DIA.	IN
INSPECTOR					SHELBY TUBE DIA.	IN

SOIL/ROCK DESCRIPTION		STRATIGRAPHIC DEPTH, F.	DEPTH, F.	SAMPLE	BLOWS/ THREE INCHES	RECOVERED	SHELBY	BORING AND SAMPLING NOTES
SURFACE ELEVATION	DATUM							
Brown CLAYEY SILT with Gravel								
				1	7 8/11	100		
		7.5		5-				
Gray SILTY CLAY with Gravel				2	4 9/12	75		
		12.5						
Gray SANDY SILT with Gravel				3	9 12/15	25		
		18.0						
Gray wet SILTY SAND with Gravel				4	12 15/17	75		
		21.0		20-				
Gray SANDY SILT with Gravel				5	18 20/27	50		
				25-				
				6	26 31/36	100		
				30-				
Bottom test boring @ 30.0'								

WATER LEVEL OBSERVATIONS

NOTED ON RODS 13 FT.
AT COMPLETION 17 FT.
AFTER HRS FT.

BORING METHOD

HSA - HOLLOW STEM AUGER
CFA - CONTINUOUS FLIGHT AUGER
DC - DRIVEN CASING
MD - MUD DRILLING
RC - ROCK CORING
CA - CASING ADVANCER

* THESE SHELBY TUBE
SAMPLES OBTAINED IN
AN AUXILIARY BORING
DRILLED A FEW FEET
FROM THIS BORING



LOG OF BORING NO. 76

CLIENT Northside Sanitary Landfill JOB NO. 21-21058
 PROJECT NAME Landfill START DATE 10-26-82
 PROJECT LOCATION Zionsville, Indiana FINISH DATE 10-26-82
 BORING LOCATION _____ BORING METHOD HSA
 FOREMAN E. Lomax ROCK CORE DIA. _____
 INSPECTOR _____ SHELBY TUBE DIA. _____

SOIL/ROCK DESCRIPTION		STRATUM DEPTH, FT.	DEPTH, FT.	STD. PENETRATION			SHELBY TUBE NO.	BORING AND SAMPLING NOTES
SURFACE ELEVATION	DATUM			SAMPLE NO.	BLOWS/3 IN. THREE 6 IN. INCREMENTS	RECOVERY, %		
Brown moist SANDY CLAY		7.0	5-	1	2 1/3	25		
Gray SANDY SILT with Gravel and sand seams (5'0 thick)			10-	2	6 9/10	75		
			15-	3	11 19/29	100		
			20-	4	19 32/35	100		
			25-	5	29 47/50 0.4	50		
Bottom test boring @ 28.8'								
				6	50 0.3	100		


Set observation well
@28.5'

WATER LEVEL OBSERVATIONS
 NOTED ON RODS 13 FT.
 AT COMPLETION _____ FT.
 AFTER _____ HRS _____ FT

BORING METHOD
 HSA - HOLLOW STEM AUGER
 CFA - CONTINUOUS FLIGHT AUGER
 DC - DRIVEN CASING
 MD - MUD DRILLING
 RC - ROCK CORING
 CA - CABLE TOOL

* THESE SHELBY TUBE
 SAMPLES OBTAINED IN
 AN AUXILIARY BORING
 DRILLED A FEW FEET
 FROM THIS BORING

FIG 5- NORTH - SOUTH SECTION, SOUTH OF ACCESS ROAD TO ALLANDERTON OF ECC SITE




12-03

APPENDIX III

The concentration of chloride and total dissolved solids and the specific conductance in groundwater samples collected from monitoring wells in the vicinity of the ECC-Site. The data were tabulated by personnel of the Indiana Department of Public Health from analyses on groundwater samples collected in late fall and early winter, 1983.

1
 TDS
 S.C
 COD

11/15
 11/15



Abundant (in 21%)
 Total dissolved solids (mg/l)
 Specific Conductance (µmhos/cm)

APPENDIX B
BORING LOGS

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
 ELEVATION 887.20 DRILLING CONTRACTOR MATECO DRILLING CO.
 DRILLING METHOD AND EQUIPMENT CME 550 RIG, HSA TO 36', 6" O.D., 3 3/4" I.D.
 WATER LEVEL AND DATE 6.5'-6/1/83-1440 HRS START 6/1/1983 FINISH 6/2/83 LOGGER D.W. LOVELL

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS BLOWS PER 6 INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	2		SS-1	18"	2-3-5-5	SANDY SILTY CLAY, BROWN AND BLACK, MOIST TOPSOIL WITH GRASS ROOTS (cl)		
	4		SS-2	14"	3-3-3-6	SILTY CLAY, MOTTLED BROWN AND GRAY, MOIST, MEDIUM STIFF, TRACE SAND		
	6		SS-3	12"	7-12-18-23	(CL)		
	8		SS-4	15"	9-14-18-19			
	10		SS-5	18"	5-8-9-12	SILTY CLAY, GRAY, MOIST, MEDIUM STIFF, SOME SAND (cl)		
	12		SS-6	21"	5-7-8-13			
	14		SS-7	18"	4-5-7-7	SILTY SAND, FINE, GRAY, WET, MEDIUM DENSE (SM)		SATURATED SOIL AT 11.5'
	16		SS-8	12"	3-7-16-14	SILTY CLAY, GRAY, WET, MEDIUM STIFF, TRACE SAND (CL-ML)		
	18		SS-9	22"	4-6-4-5			
	20		SS-10	21"	3-4-7-9	SILTY CLAY, GRAY, WET, SOME SAND, MEDIUM STIFF, TRACE GRAVEL (cl)		
	22							
	24							
	26		SS-11	16"	11-18-22	SAND, FINE TO MEDIUM, GRAY, MOIST TO WET, DENSE (sp-sw)		SAND BLINDING INTO BOTTOM OF HOLLOW-STEM-PILGER
	28							WATER LEVEL RISING TO ~6 FT BELOW GROUND SURFACE
	30		SS-12	11"	6-8-10	SILTY CLAY, MOTTLED TAN AND BROWN, MOIST TO WET, STIFF (CL-ML)		



PROJECT NUMBER W65230.C3	BORING NUMBER ECC-1A	SHEET 2 OF 2
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
ELEVATION 887.20 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, HSA TO 36', 5 1/2" ROTARY BIT TO 40'
WATER LEVEL AND DATE 3.5' - 6/2/83 - 0900 HRS START 6/1/83 FINISH 6/2/83 LOGGER D.W. LOVELL

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS BLOWS.. PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
32								
34		34.5						
36		35.7	SS-13	10"	25-41-57 1/3"	SILTY CLAY, BROWN-GRAY, MOIST, SOME SAND, TRACE GRAVEL, HARD (CL)		PUSHED 6" CASING TO ~22 FT. THEN DROVE CASING W/300# HAMMER TO ~29 FT. DRILLED W/5 1/2" ROTARY BIT FROM 36 TO 40 FT.
38								
40						BOTTOM OF BORING 40.0'		SET MONITORING WELL TIP AT 28.5 FT.



PROJECT NUMBER W65230.C3	BORING NUMBER ECC-1C	SHEET 1 OF 6
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
ELEVATION 886.70 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME-550 RIG, HSA TO 8', ROTARY BIT W/CLEAR WATER TO 30'
WATER LEVEL AND DATE 3.9'-6/3/83-0800HRS START 6/2/83 FINISH 6/3/83 LOGGER I.H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS BLOWS PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
2						NOT SAMPLED FROM 0' TO 23.5'		OFFSET AND DRILLED WITHOUT SAMPLING TO 23.5 FT - SEE ECC-1A LOG FOR SHALLOW SOIL UNITS SET HSA'S TO 8' THEN PUSHED 6" CASING TO 8'
4								
6								
8								
10								
12								
14								
16								
18								
20								
22								
23.5						~23.5		HOLE CAVED BELOW 23.5' PUSHED 6" CASING TO 18' DROVE 6" CASING TO 30' WITH 300# HAMMER
24		SS-1	18"	6-10-13		SAND, FINE TO COARSE, GRAY, WET, MEDIUM DENSE, SOME FINE GRAVEL (SW)		
25.0								
26								
28								



PROJECT NUMBER <u>W65230.C3</u>	BORING NUMBER <u>ECC-1C</u>	SHEET <u>2</u> OF <u>6</u>
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
ELEVATION 886.70 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME-550 RIG, 3 1/2" DRAG BIT, BENTONITE MUD BELOW 30'
WATER LEVEL AND DATE 9.33' - 6/4/83 - 0600 HRS START 6/2/83 FINISH 6/3/83 LOGGER I. H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	BLOWS PER 6-INCHES	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	30	29.5	SS-2	10"	14-16-18	<u>SAND, FINE, GRAY, WET, DENSE, SOME SILT (SM)</u>		SET 4" CASING TO 30' INSIDE OF 6" CASING, THEN DROVE 4" CASING TO 34'
	32	31.0						
	34	34.5	SS-3	14"	27-52-55	<u>SILTY CLAY, GRAY, MOIST, HARD, SOME SAND, TRACE GRAVEL (CL-ML)</u>		VERY HARD DRILLING - BELOW 32.5'
	36	36.0						
	38	39.5				<u>CLAY, GRAY, MOIST, HARD, WITH FINE TO COARSE SAND AND FINE GRAVEL (CL)</u>		
	40	41.0	SS-4	17"	26-32-60			
	42					<u>SILTY CLAY, GRAY, MOIST, HARD, TRACE SAND (CI)</u>		
	44	44.5	SS-5	16"	28-39-60			
	46	46.0				<u>CLAY, GRAY, MOIST, HARD, TRACE SAND (CI)</u>		
	48	49.5						
	50	51.0	SS-6	18"	13-21-25	<u>SILTY CLAY, MOTTLED GRAY AND BROWN, MOIST, HARD, TRACE SAND (CL-ML)</u>		
	52							
	54	54.5	SS-7	18"	16-24-29			
	56	56.0						
	58							



PROJECT NUMBER

WG5230.C3

BORING NUMBER

ECC-1C

SHEET 3 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
ELEVATION 886.70 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 30'
WATER LEVEL AND DATE 2.3'-6/5/83-0630 HRS START 6/2/83 FINISH 6/8/83 LOGGER I.H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-8"-6" TNT BLOWS PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	59.5'					<u>SILTY CLAY, BLUE-GRAY, MOIST TO WET, HARD</u>		
60	61.0	SS-8	12"	11-17-29		(CL)		
62	62.0					<u>SAND, FINE TO COARSE, GRAY, WET, DENSE</u>		
	63.5	SS-9	18"	18-13-19		(SP)		
64	64.5							
	65.5	SS-10	13"	25-52		<u>SILTY CLAY, GRAY, MOIST, HARD, SOME FINE TO COARSE SAND</u>		
66						(CL)		
68								
70	68.5					<u>SILT, GRAY, MOIST, HARD, TRACE CLAY, TRACE SAND</u>		
	70.5	SS-11	12"	46-57		(ml)		
72								
74	74.5					<u>SILT, BROWN, MOIST, HARD, WITH FINE TO COARSE SAND AND FINE GRAVEL</u>		
76	76.0	SS-12	12"	30-24-30		(ML)		
78								
80	79.5					<u>SILT, BROWN, MOIST, HARD WITH FINE TO COARSE SAND AND FINE GRAVEL</u>		
	80.5	SS-13	11"	46-60/5"		(ML)		
82								
84	84.5					<u>SILT, BROWN, MOIST, HARD, TRACE FINE SAND</u>		
86	86.0	SS-14	18"	23-31-45		(ml)		
88								

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATIONLOCATION NORTHWEST CORNERELEVATION 886.70DRILLING CONTRACTOR MATECO DRILLING CO.DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 30'WATER LEVEL AND DATE 2.7'-6/7/83-0715 HRS START 6/2/83 FINISH 6/3/83 LOGGER I.H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" 1" BLOWS PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	90	89.5				<u>SILTY CLAY</u> , BROWN-GRAY, MOIST, VERY STIFF, TRACE SAND AND FINE GRAVEL (cl)		
	92	91.0	SS-15	18"	16-20-28			
	94	94.5				<u>SILTY CLAY</u> , DARK GRAY, MOIST, HARD, TRACE SAND, TRACE FINE GRAVEL (cl)		EASIER DRILLING - FEWER COBBLES NOTICED BELOW 96'
	96	96.0	SS-16	18"	24-42-60			
	100	95.5				<u>CLAYEY SILT</u> , BROWN-GRAY, MOIST, HARD, SOME SAND, TRACE FINE GRAVEL (cl-m)		ROUGH DRILLING COBBLES BELOW 120'
	102	100.0	SS-17	5"	60/5"			
	104	104.5				<u>SILT</u> , DARK GRAY, MOIST, HARD TRACE CLAY, TRACE FINE GRAVEL (ml)		EASIER DRILLING BELOW 106.5'
	106	105.5	SS-18	11"	37-60/5"			
	108	109.5				<u>SAND</u> , FINE, BROWN, WET, DENSE (sp)		
	110		SS-19	18"	39-36-46			
	112	111.0				<u>SILTY CLAY</u> , BROWN, MOIST TO WET, HARD, TRACE SAND (cl)		
	114	114.5						
	116	115.5	SS-20	11"	38-60/5"	<u>SILT</u> , GRAY, MOIST, HARD, SOME SAND, SOME FINE GRAVEL (ml)		COBBLES AT ~116'
	118							



PROJECT NUMBER W65230.C3	BORING NUMBER ECC-1C	SHEET 5 OF 6
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
ELEVATION 886.70 DRILLING CONTRACTOR MATELO DRILLING CO
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 30'
WATER LEVEL AND DATE _____ START 6/2/83 FINISH 6/3/83 LOGGER I. L. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	Blows PER 12-INCHES	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		119.5						
	120	120.0	SS-21	4"	60/4"	SILTY CLAY, MOTTLED BROWN AND GRAY, MOIST, HARD, SOME SAND, TRACE FINE GRAVEL (cl)		ROUGH DRILLING BELOW 120'
	122							
	124	124.5						
		125.0	SS-22	5"	60/5"	CLAYEY SILT, BROWN-GRAY, MOIST, HARD, SOME SAND TRACE FINE GRAVEL (cl-m1)		
	126							
	128							
		129.5						
	130	130.0	SS-23	2"	60/4"	CLAYEY SILT, DARK GRAY, MOIST HARD, SOME SAND, TRACE FINE GRAVEL (cl-m1)		ROUGH DRILLING ROD CHATTER
	132							
		134.5						
		135.0	SS-24	2"	60/5"	SILT, GRAY, MOIST TO WET, TRACE FINE GRAVEL (m1)		
	136							
	138							
		139.5						
	140		SS-25	18"	22-25-31	SILTY CLAY, BLUE-GRAY, MOIST VERY STIFF, TRACE SAND (CL)		EASIER DRILLING BELOW 139'
	142	141.0						
		144.5						
	144		SS-26	18"	20-40-47			
		146.0				SAND, FINE, WET, DENSE, TRACE SILT (sp)		
	148							

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHWEST CORNER
 ELEVATION 886.70 DRILLING CONTRACTOR MATECO DRILLING CO.
 DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 30'
 WATER LEVEL AND DATE _____ START 6/2/83 FINISH 6/8/83 LOGGER J. H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-8"-6" BLOWS PER 12-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	150	149.5	SS-27	11"	54-60/5"	CLAYEY SAND, GRAY, WET, DENSE WITH WEATHERED LIMESTONE FRAGMENTS (SC)		ROD CHATTER AND VERY DIFFICULT DRILLING BELOW 150'
	152	150.5						
	154	154.5	SS-28	12"	54-40-40	SILTY SAND, FINE TO COARSE, GRAY, WET, DENSE, SOME FINE GRAVEL (SM-SW)		PROBLEMS WITH HOLE CAVING FROM 157 TO 159'
	156	156.0						
	158	159.5	SS-29	7"	26-40-69	GRAVEL, FINE TO MEDIUM, GRAY, WET, DENSE, WITH FINE TO COARSE SAND, TRACE SILT (GW-SW)		PROBLEMS WITH HOLE CAVING
	160	161.0						
	162							
	164	165.0						
	166	165.9	SS-30	10"	32-60/5"	SILTY CLAY, GRAY, MOIST, SOFT (CI) TOP OF ROCK AT 166.0'		REAMED HOLE WITH 5 1/4" ROLLER BIT, THEN SET 4" CASING TO 165'
	168	166.0	NX Rock CORE	4'10"	N.A.	LIMESTONE, LIGHT GRAY TO WHITE, HARD, UNWEATHERED, FRACTURED FROM 168.5-170'		
	170	171.0				BOTTOM OF BORING 171.0'		



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-2C

SHEET 1 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTH
ELEVATION 886.94 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME-550 RIG, 3 3/4" I.D. HSA TO 36', ROTARY W/BENTONITE MUD FEED 36'
WATER LEVEL AND DATE 6/13/83 START 6/13/83 FINISH 6/17/83 LOGGER B.N. ZVIALEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-8" SPT Blows PER 1'-10" HES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
2		SS-1	18"	7-3-2-3		SILTY CLAY, DARK BROWN, MOIST, SOME SAND, SOME ORGANICS, ROOTS AND GRASS (CL-OI) 1.0'		
4		SS-2	24"	4-6-10-14				
6		SS-3	24"	5-7-10-13		SILTY CLAY, GRAY, MOIST, STIFF, TRACE SAND, TRACE FINE GRAVEL (CL-ML)		
8		SS-4	20"	8-11-10-10				
10		SS-5	18"	4-5-7-9				
12		SS-6	20"	5-6-7-9				
14		SS-7	24"	3-4-6-8				
16		SS-8	19"	3-4-4-8				WATER AT 15.0'
18		SS-9	15"	8-9-11-13		SAND, FINE TO COARSE, GRAY, WET, MEDIUM DENSE, GRADES TO FINE GRAVEL (SP)		
20		SS-10	24"	7-9-10-10				
22		SS-11	10"	8-9-12-13		SAND, FINE TO COARSE, GRAY, WET, MEDIUM DENSE TO DENSE, SOME FINE GRAVEL (SW)		
24		SS-12	24"	11-11-13-19				
26		SS-13	0"	12-11-10-13				
28		SS-14	7"	10-10-12-17				
30		SS-15	0"	18-17-19-21				



PROJECT NUMBER

WG5230.C3

BORING NUMBER

ECC-2C

SHEET 2 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATIONLOCATION NORTHELEVATION 886.94DRILLING CONTRACTOR MATECO DRILLING CO.DRILLING METHOD AND EQUIPMENT LME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 36'WATER LEVEL AND DATE START 6/13/83 FINISH 6/17/83 LOGGER R.N. ZVABLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 5"-6" INT BLOWS PER 12-INCHES	SOIL DESCRIPTION		SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY		NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL			
							31.5'		
	32	X	SS-16	24"	28-18-17-22	SILTY SAND, FINE TO COARSE, GRAY, WET, DENSE (SM)		SET 6" CASING TO 34' SET 4" CASING TO 35'	
	34	X	SS-17	15"	20-16-18-26				
	36	X	SS-18	16"	13-20-17-32				
	38	38.0				SILTY CLAY, GRAY, MOIST, VERY STIFF TO HARD, SOME FINE GRAVEL (cl-m)		SET 4" CASING TO 39' HARD, SLOW DRILLING BELOW 40'	
	40	X	SS-19	12"	13-35-50				
	42	40.0							
	44	44.5				CLAY, GRAY, MOIST, VERY STIFF TO HARD, SOME FINE TO COARSE SAND (CL)			
	46	X	SS-20	18"	28-46-60				
	48	46.0							
	50	49.5				CLAY, GRAY, MOIST, VERY STIFF TO HARD, SOME FINE TO COARSE SAND (CL)			
	52	X	SS-21	18"	20-26-39				
	54	51.0							
	56	54.5				CLAY, GRAY, MOIST TO WET, STIFF WITH 6" SILTY SAND LENS (cl and sm)			
	58	X	SS-22	18"	27-24-23				
		56.0							
							~58'		



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-2C

SHEET 3 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTH
ELEVATION 886.94 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 55D RIG, ROTARY WITH BENTONITE MUD BELOW 36'
WATER LEVEL AND DATE _____ START 6/13/83 FINISH 6/17/83 LOGGER B.N. ZVIBLAMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6-8-8 111 Blows PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	60	59.5				<u>SILT</u> , OLIVE GREEN, MOIST, STIFF, SOME FINE SAND (ml)		
	62	61.0	SS-23	18"	12-16-24			
	64	64.5				<u>SILTY SAND AND SANDY SILT</u> , OLIVE GREEN, MOIST, STIFF TO HARD (sm and ml)		
	66	65.5	SS-24	11"	20-60/5"			
	68					~68'		
	70	69.5				<u>SILTY CLAY</u> , OLIVE GREEN, MOIST, VERY STIFF TO HARD (cl)		
	72	70.5	SS-25	12"	37-60/5"			
	74	74.5				<u>CLAY</u> , OLIVE GRAY, MOIST, HARD (cl)		
	76	75.5	SS-26	12"	26-60/5"			
	78							
	80	79.5				<u>CLAYEY SILT</u> , OLIVE GRAY, MOIST, HARD (ML-CL)		
	82	80.5	SS-27	12"	50-60/5"			
	84	84.5				<u>SILTY CLAY</u> , BROWN, DRY TO MOIST (cl)		
	86	85.5	SS-28	11"	38-60/5"			
	88							



PROJECT NUMBER <u>W65230.C3</u>	BORING NUMBER <u>ECC-2C</u>	SHEET <u>4</u> OF <u>6</u>
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTH
ELEVATION 886.94 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 36'
WATER LEVEL AND DATE _____ START 6/13/83 FINISH 6/17/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	Blows per 6-INCHES	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	90	89.5 X	SS-29	18"	24-43-60 1/6	SILTY CLAY, GRAY, MOIST, HARD, TRACE FINE GRAVEL (cl)		
	92	91.0						
	94	94.5 X	SS-30	16"	28-49-60 1/4	CLAY, GRAY, MOIST, HARD, SOME SILT (cl)		
	96	96.0						
	98	99.5 X					~98.0'	SOFTER DRILLING BELOW 98.0'
	100	100.5 X	SS-31	10"	55-60 1/5	SAND, FINE TO COARSE, BROWN, VERY DENSE, TRACE FINE GRAVEL (SP-SM)		
	102	100.5						
	104	104.5 X	SS-32	9"	43-60 1/3	SAND, FINE TO MEDIUM, BROWN, VERY DENSE (sp)		
	106	105.4						
	108						~109.0'	
	110	109.5 X	SS-33	18"	20-44-56	SANDY SILT AND SILTY SAND, FINE, GRAY, WET (ml and sm)		
	112	111.0						
	114	114.5 X						~114.0'
	116	116.0 X	SS-34	18"	14-28-37	CLAYEY SILT, GRAY, MOIST, VERY STIFF (ml-cl)		
	118							HARDER DRILLING BELOW 114.0'



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-2C

SHEET 5 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATIONLOCATION NORTHELEVATION 886.94DRILLING CONTRACTOR MATECO DRILLING CO.DRILLING METHOD AND EQUIPMENT CME-550 RIG, ROTARY WITH BENTONITE MUD BELOW 36'WATER LEVEL AND DATE _____ START 6/13/83 FINISH 6/17/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	6"-6"-6" (N)	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		119.5						
	120	X	SS-35	18"	22-44-60 1/4	SILTY CLAY, DARK GRAY, MOIST, HARD (CL)		
	122	120.9						
	124	124.5						
	126	X	SS-36	11"	34-60 1/5"	CLAY, GRAY, MOIST, HARD, TRACE FINE SAND (ch)		
	128	125.5						
		128.5						
	130	X	SS-37	0"	60 1/5"			
		129.9						
	132							
	134	134.5						
	136	X	SS-38	18"	42-56-54	CLAYEY SILT, GRAY, MOIST, HARD TRACE FINE SAND, TRACE ORGANICS (ROOTS) (ml-ol)		
		136.0						
	138							
	140	X	SS-39	18"	12-15-21	CLAY, BLUE-GRAY, MOIST, VERY STIFF, TRACE SILT (cl)		
	142	141.0						
	144	144.5						
	146	X	SS-40	18"	25-17-24	CLAY, GRAY, MOIST, VERY STIFF, SOME FINE TO COARSE SAND (CL-ML)		
		146.0						
	148							

ROD CHATTER DURING
DRILLING FROM
126.0' TO 128.0'



PROJECT NUMBER <u>W65230.C3</u>	BORING NUMBER <u>ECC-2C</u>	SHEET <u>6</u> OF <u>6</u>
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTH
ELEVATION 886.94 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 36'
WATER LEVEL AND DATE _____ START 6/13/83 FINISH 6/17/83 LOGGER B.N. ZVIBLERNAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-6"-6" (IN)	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	150	149.5	SS-41	18"	23-27-32	SAND, FINE TO MEDIUM, GRAY, WET, VERY DENSE, SOME LIMESTONE CHIPS (SM)		
	152	151.0						
	154	154.5	SS-42	0"	60/4"			
	156	154.9						
	158					SAND, FINE TO COARSE, GRAY, WET, VERY DENSE, SOME FINE GRAVEL (SP-GP)		
	160	160.0	SS-43	4"	60/5"			
		160.5						
	162	162.5				TOP OF ROCK AT 162.5' ✓		
	164		↑ NX ROCK CORE ↓	3'	N.A.	LIMESTONE, LIGHT GRAY TO WHITE, HARD, UNWEATHERED		
	166	165.5				BOTTOM OF BORING ✓ 165.7'		



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-3A

SHEET

1 OF 1

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATIONLOCATION SOUTHEAST CORNERELEVATION 876.60

DRILLING CONTRACTOR

MATEO DRILLING CO.DRILLING METHOD AND EQUIPMENT 3 1/4" I.D. Hollow Stem AugersCME-45C TRAILER MOUNTED DRILL RIGWATER LEVEL AND DATE 6'-6/14/83 - 8:50 AMSTART 6/14/83FINISH 6/14/83LOGGER I. H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 8-10 Blows PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	2'		SS-1	12"	7 4 2 6	SILTY CLAY, BROWN TO BLACK, DRY TO MOIST, STIFF, TRACE ORGANICS (CL)		
	4'		SS-2	15"	3 3 4 4			
	6'		SS-3	4"	2 4 7 6			
	8'		SS-4	12"	3 3 2 2	SAND, FINE TO COARSE, BROWN, WET, LOOSE TO MEDIUM DENSE, SOME SILT, TRACE FINE TO COARSE GRAVEL (SW-SM)		WATER AT 6.0' NOTED WHILE DRILLING WITH HOLLOW STEM AUGERS
	10'		SS-5	18"	4 6 6 7			
	12'		SS-6	24"	3 3 4 5			
	14'		SS-7	24"	8 19 15 12			
	16'		SS-8	24"	4 11 10 15			
	18'		SS-9	20"	13 25 11 7	SILTY CLAY, GRAY, MOIST, STIFF, TRACE FINE TO COARSE SAND (CL-ML)		
	20'		SS-10	18"	5 7 9 13			
	22'		SS-11	20"	5 10 13 19			
	24'		SS-12	24"	16 23 42 52	SILTY SAND, FINE TO MEDIUM, GRAY, MOIST, DENSE (SWL)		
						SILTY CLAY, GRAY, MOIST, HARD, SOME SAND, TRACE GRAVEL (CL)		
						BOTTOM OF BORING AT 24.0' ↗		



PROJECT NUMBER <u>W65230.C3</u>	BORING NUMBER <u>ECC-3C</u>	SHEET <u>1</u> OF <u>6</u>
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTHEAST
ELEVATION 876.75 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD
WATER LEVEL AND DATE _____ START 6/22/83 FINISH 6/24/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 0-6-6 Blows per 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY				DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	2							OFF-SET AND DRILLED WITHOUT SAMPLING TO 23.5' SEE ECC-3A LOG FOR SHALLOW SOIL UNITS
	4							
	6							
	8							
	10							
	12							
	14							
	16							
	18							
	20							
	22							SET 4" CASING TO 23.5'
	24							
	26							
	27.0							
	28		SS-1	0"	17-13-60/5"			
	28.5							
	30							



PROJECT NUMBER W65230.C3	BORING NUMBER ECC-3C	SHEET 2 OF 6
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTHEAST
ELEVATION 876.75 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD
WATER LEVEL AND DATE _____ START 6/22/83 FINISH 6/24/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS <small>5" 6"-8" 44T BLOWS PER 6-INCHES</small>	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
32								
34		34.5				<u>SILTY CLAY, GRAY, MOIST, VERY STIFF TO HARD</u> <u>(CL-ML)</u>		
36		X 36.0	SS-2	14"	16-41-47			
38								
40		39.5				<u>SILTY CLAY, GRAY BROWN, MOIST, VERY STIFF TO HARD</u> <u>(cl-ml)</u>		
42		X 41.0	SS-3	17"	20-22-28			
44								
46		44.5				<u>SILTY CLAY, DARK GRAY, MOIST, VERY STIFF</u> <u>(cl-ml)</u>		
48		X 46.0	SS-4	18"	12-19-26			
50								
52		49.5				<u>SILTY CLAY, MOTTLED OLIVE GREEN, MOIST, VERY STIFF TO HARD, TRACE SAND</u> <u>(cl-ml)</u>		
54		X 51.0	SS-5	18"	15-17-27			
56								
58		54.5				<u>CLAY, OLIVE, MOIST, HARD, TRACE SAND, TRACE GRAVEL</u> <u>(cl)</u>		
		X 56.0	SS-6	18"	19-35-39			



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-3C

SHEET 3 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATIONLOCATION SOUTHEASTELEVATION 876.75DRILLING CONTRACTOR MATECO DRILLING CO.DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUDWATER LEVEL AND DATE _____ START 6/22/83 FINISH 6/24/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS Blows PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	60	59.5				CLAY, OLIVE, MOIST TO DRY, HARD, TRACE SILT (cl-)		
		SS-7	11"	24-60/5"				
	62	60.5						
	64	64.5				SILTY CLAY, GRAY, MOIST, HARD, SOME FINE TO COARSE SAND, TRACE FINE GRAVEL (CL-ML)		
	66	SS-8	17"	39-48-60/4"				
		65.9						
	68	69.5				SILT, OLIVE GRAY, DRY, HARD, TRACE FINE SAND (ml)		
	70	SS-9	11"	59-60/5"				
		70.5						
	72							
	74	74.5				CLAY, GRAY, DRY, HARD, TRACE SILT, TRACE FINE SAND (cl)		HARD SLOW DRILLING 76.0' - 79.0'
	76	SS-10	11"	29-60/5"				
		75.5						
	78	79.5				CLAYEY SILT, GRAY, MOIST, HARD, TRACE FINE SAND, TRACE FINE GRAVEL (cl-m)		
	80	SS-11	17"	28-37-47				
		81.0						
	82							
	84	84.5				CLAYEY SILT, GRAY, MOIST, HARD, GRADES TO SILTY SAND, FINE, GRAY, DENSE, GRADES TO ORGANIC CLAY, BLACK TO DARK GRAY, HIGHLY PLASTIC, SOFT (ml) and (sm) and (ch-oh)		SOFT DRILLING 85-89.5' WOOD AND ORGANICS IN MUD RETURN
	86	SS-12	18"	42-53-45				
		86.0						
	88							



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-3C

SHEET 4 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATIONLOCATION SOUTHEASTELEVATION 876.75DRILLING CONTRACTOR MATECO DRILLING CO.DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUDWATER LEVEL AND DATE START 6/22/83 FINISH 6/24/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-6"-6" (N)	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	89.5							
90	X	SS-13	18"		31-43-44	CLAYEY SILT, GRAY, MOIST, HARD, TRACE FINE GRAVEL, GRADES TO SILTY SAND, FINE, GRAY, WET (ml-sm)		
92	91.0							
94	X	SS-14	5"		60/6"	SANDY SILT, DARK GRAY, MOIST, HARD, TRACE FINE GRAVEL (ml-sm)		
96	95.0							
98								
100	X	SS-15	0"		60/6"			
102	100.0							
104								
106	X	SS-16	18"		32-48-43	CLAYEY SILT, GRAY, MOIST, HARD, TRACE FINE SAND (ML)		
108	106.0							
110	X	SS-17	5"		120/5"	CLAYEY SILT, GRAY, MOIST, HARD, TRACE FINE SAND (ml)		SOFTER DRILLING 108.0' - 109.5'
112	109.9							ROD CHATTER AT ~112'
114								
116	X	SS-18	2"		60/4"	SANDY SILT, GRAY, DRY, HARD, TRACE CLAY, TRACE ORGANICS (ml-sm)		HARD DRILLING 115.0' - 119.0'
118	114.9							



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-3C

SHEET 5 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTHEAST
ELEVATION 876.75 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CHE 550 RIG, ROTARY WITH BENTONITE MUD
WATER LEVEL AND DATE START 6/22/83 FINISH 6/24/83 LOGGER B.N. ZUILLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-6"-6" (N)	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	120	119.5 119.9	SS-19	5"	60/5"	SANDY SILT, GRAY, MOIST, HARD, TRACE FINE GRAVEL (m/-sm)		SOFTER DRILLING 119'-124'
	122							
	124	124.5						
	126	126.0	SS-20	18"	32-39-51	SILTY CLAY, BROWN, MOIST, HARD, TRACE FINE SAND AND GRAVEL (CL)		SOFT DRILLING 125'-130'
	128							
	130	129.5 131.0	SS-21	18"	20-24-31	SILTY CLAY, BROWN, MOIST, HARD (CL)		SOFT DRILLING 130'-135'
	132							
	134	134.5						
	136	136.0	SS-22	18"	30-28-56	SILTY CLAY, BROWN, MOIST, HARD (CL) 135.5'		
	138	138.5				SILTY SAND, FINE TO MEDIUM, GRAY, DENSE (sm)		
	140	140.9	SS-23	16"	33-44-60 1/4"	SAND, FINE, GRAY, MOIST, DENSE GRADES TO A SILTY SAND (sp-sm)		
	142							
	144	144.5						
	146	145.0	SS-24	0"	120/6"			HARD, SLOW DRILLING 147'-154'
	148							



PROJECT NUMBER WG5230.C3	BORING NUMBER ECC-3C	SHEET 6 OF 6
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTHEAST
ELEVATION 876.75 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD
WATER LEVEL AND DATE _____ START 6/22/83 FINISH 6/24/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-6"-6" (IN)	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY				DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	150	149.5	SS-25	18"	30-44-55	CLAY, GRAY-BROWN, MOIST, HARD (cl)		
	152	151.0						
	154					BOTTOM OF BORING 154.5		
	156					TOP OF ROCK		'NX' CORE BARREL BROKEN - COULD NOT GET WATER CIRCULATION TO CORE ROCK



PROJECT NUMBER W65230.C3	BORING NUMBER ECC-4C	SHEET 1 OF 6
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION EAST
ELEVATION 884.62 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME-45 TRAILER MOUNTED RIG, 3 1/4" I.D. HOLLOW STEM AUGERS TO 26'
WATER LEVEL AND DATE 10.0'-6/14/83-1600 HRS START 6/14/83 FINISH 6/21/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	8-8-8 HH Blows PER 6-INCHES	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	2		SS-1	18"	5-4-4-7	FILL		
	4		SS-2	20"	6-4-7-7			4.0'
	6		SS-3	16"	3-4-5-6	SILT, BLACK, SOME ORGANICS, TRACE SAND, MOIST (ml-ol)		5.5'
	8		SS-4	16"	4-5-9-11	CLAYEY SILT, GRAY, MOIST, STIFF, TRACE FINE TO COARSE SAND (ML)		9.5'
	10		SS-5	18"	7-12-12-10			
	12		SS-6	13"	10-14-20-18	SAND, FINE TO COARSE, GRAY, SOME CLAY (SC)		WATER AT 10.0'
	14		SS-7	12"	25-37-34-33	SAND, FINE TO COARSE, GRAY, SOME CLAY, GRADES TO SILTY SAND (SC)		
	16		SS-8	13"	15-22-30-45			
	18		SS-9	20"	30-33-40-47			17.0'
	20		SS-10	11"	40-60/5	SILTY CLAY, GRAY, MOIST, HARD, INTERBEDDED WITH SILTY FINE SAND (CL)		
	22		SS-11	24"	25-33-30-32			21.5'
	24		SS-12	20"	18-22-24-32	CLAY, GRAY, MOIST, HARD, SOME FINE TO COARSE SAND (CL)		
	26		SS-13	24"	17-23-26-30			
	28							PULLED HOLLOW STEM AUGERS AND SET 4" CASING TO 25' STARTED DRILLING WITH 3 3/4" ROLLER BIT AND WATER

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION EAST
 ELEVATION 884.62 DRILLING CONTRACTOR MATECO DRILLING CO.
 DRILLING METHOD AND EQUIPMENT CME 45 TRAILER MOUNTED RIG, 3 3/4" ROLLER BIT WITH BENTONITE 26'-70.5'
 WATER LEVEL AND DATE START 6/14/83 FINISH 6/21/83 LOGGER I. H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" 6" 6" TNT BLows PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	30	29.5	SS-14	9"	6-26-44	CLAYEY SILT, GRAY, MOIST, HARD, SOME SAND, TRACE GRAVEL (m/-cl)		STARTED USING BENTONITE MUD WITH ROLLER BIT
	32	31.0						VERY SLOW DRILLING
	34	34.5	SS-15	14"	27-46-47	CLAYEY SILT, GRAY, MOIST, HARD, TRACE SAND, TRACE GRAVEL (m/-cl)		
	36	36.0						VERY SLOW DRILLING
	38	39.5	SS-16	15"	34-50-60 1/5	CLAY, GRAY-BLUE, MOIST, HARD, SOME FINE TO COARSE SAND (CL)		
	40	41.0						VERY SLOW DRILLING
	42	44.5	SS-17	15"	17-27-38	SILTY CLAY, GRAY-BLUE, MOIST, HARD, TRACE SAND, TRACE GRAVEL (cl-m)		
	44	46.0						VERY SLOW DRILLING
	46	49.5	SS-18	18"	20-30-40	SILTY CLAY, GRAY-BLUE, MOIST, HARD, TRACE SAND, TRACE GRAVEL (cl-m)		
	48	51.0						SWITCHED FROM 3 3/4" ROLLER BIT TO 3 1/2" DRAG BIT TO SPEED UP DRILLING THROUGH THE GLACIAL TILL
	50	54.5	SS-19	18"	10-17-23	CLAY, OLIVE GREEN TO GRAY, MOIST, STIFF (CL)		
	52	56.0						
	54							
	56							
	58							



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-4C

SHEET 3 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION EAST
ELEVATION 884.62 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME-550 RIG, ROTARY WITH BENTONITE MUD BELOW 70.5'
WATER LEVEL AND DATE _____ START 6/14/83 FINISH 6/21/83 LOGGER I.H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 5" 6" 8" -HNT Blows per 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	60	59.5				<u>SAND, FINE, BROWN TO GREEN, MOIST, DENSE</u> (sp) 60.5'		
	62	61.0	SS-20	18"	17-23-21	<u>SILTY CLAY, GRAY, MOIST, HARD</u> (cl)		
	64	64.5						
	66	65.5	SS-21	11"	25-60/5"	<u>SILTY CLAY, BROWN TO GRAY, MOIST, HARD, WITH FINE SILTY SAND LENSES</u> (cl-mI)		
	68							
	70	69.5						
	72	70.5	SS-22	10"	30-60/5"	<u>SAND, FINE, GRAY, MOIST, DENSE, SOME SILT</u> (sp-sm)		STARTED USING CME-550 RIG AT 70.5'
	74	74.5						
	76	75.1	SS-23	8"	50-60/2"	<u>CLAYEY SILT, OLIVE-GRAY, DRY, HARD, TRACE SAND, TRACE GRAVEL</u> (ml-cl)		BIT CLOGGED
	78							
	80	79.5						
		79.8	SS-24	0"	60/3"			
	82							
	84	84.5						
	86	85.9	SS-25	12"	37-60/5"	<u>CLAYEY SILT, GRAY, DRY TO MOIST, HARD, TRACE SAND</u> (ml)		SLOW, HARD DRILLING
	88							



PROJECT NUMBER

W65

BORING NUMBER

ECC-4C

SHEET

4 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION EAST
ELEVATION 884.62 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 70.5'
WATER LEVEL AND DATE _____ START 6/14/83 FINISH 6/21/83 LOGGER B.N. ZUBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	6" 6" 6" 11" BLOWS PER 6-INCHES	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	89.5							
	90	X	SS-26	14"	49-28-60 1/2"	SILTY CLAY, GRAY, MOIST, HARD, GRADES TO SILTY FINE SAND (cl-mI)		
	90.6							
	92							
	94							
	94.5	X	SS-27	17"	49-53-60 1/5"	CLAYEY SILT, GRAY, MOIST, HARD (ML)		
	96							
	95.9							
	98							
	99.5	X	SS-28	6"	60/6"	SANDY CLAY, DARK GRAY, MOIST, HARD, SOME SILT (SC)		
	100							
	100.0							
	102							
	104							
	104.5	X	SS-29	16"	31-33-60 1/4"	SILTY CLAY, GRAY, MOIST, HARD, TRACE FINE SAND (cl)		
	106							
	105.9							
	108							
	109.5	X	SS-30	0"	60/5"			
	110							
	109.9							
	112							
	114							
	114.5	X	SS-31	11"	41-60 1/5"	SANDY SILT, GRAY, MOIST, DENSE (ml-sm)		
	116							
	115.5							
	118							

SLOW, HARD DRILLING
102.0' - 104.0'



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-4C

SHEET 5 OF 6

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION EAST
ELEVATION 884.62 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 70.5'
WATER LEVEL AND DATE _____ START 6/14/83 FINISH 6/21/83 LOGGER B.N. ZVIBLERNAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-8"-6" Blows PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	120	119.5 119.8	SS-32	3"	60/3"	SILTY SAND, FINE, GRAY, MOIST, VERY DENSE, SOME CLAY (SM)		
	122							
	124	124.5 124.9	SS-33	3"	60/3"	SILTY SAND, FINE, GRAY, MOIST, VERY DENSE (SM)		
	126							
	128							
	130	129.5 129.9	SS-34	1"	60/4"	SANDY SILT, BROWN-GRAY, MOIST, VERY DENSE, TRACE CLAY (ml)		
	132							HARD DRILLING 130.0' TO 135.0'
	134	134.5 136.0	SS-35	18"	27-36-48	SILTY CLAY, GRAY, MOIST, HARD (cl)		
	136							
	138							
	140	139.5 141.0	SS-36	18"	22-26-31	SILTY CLAY, BROWN, MOIST, HARD, SOME SAND (cl)		
	142							
	144	144.5 145.9	SS-37	17"	34-54-60 1/5"	SILTY CLAY, BROWN, MOIST, HARD, SOME SAND, OCCAS. SAND LENSES (cl)		
	146							
	148							

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION EAST
ELEVATION 884.62 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, ROTARY WITH BENTONITE MUD BELOW 70.5'
WATER LEVEL AND DATE _____ START 6/14/83 FINISH 6/21/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS -6"-8"-10" BLOWS PER 6-INCHES	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
	150	149.5						
		X	SS-38	12"	39-47-60/5"	SAND, FINE, GRAY, WET, VERY DENSE, SOME SILT (SM)		
	152	150.9						
	154	154.5						
		X	SS-39	8"	53-60/5"	SAND, FINE TO COARSE, GRAY, WET, VERY DENSE, TRACE SILT (SM)		
	156	155.5						
	158							
	160	161.0				CLAY, LIGHT GRAY, MOIST, HARD		
		X	SS-40	10"	34-60/4"	TOP OF ROCK ↴ 161.9'		SLOW DRILLING 160-162'
	162	161.9 162.9				LIMESTONE, LIGHT GRAY TO WHITE, HARD, UNWEATHERED		
	164	X	NX ROCK CORE	3.0'	N.A.	BOTTOM OF BORING ↴ 165.9'		
	166	165.9						



PROJECT NUMBER

W65230.C3

BORING NUMBER

ECC-5A

SHEET 1 OF 2

SOIL BORING LOG

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTHWEST
ELEVATION 887.28 DRILLING CONTRACTOR MATECO DRILLING
DRILLING METHOD AND EQUIPMENT CME 550 RIG, 3 3/4" HOLLOW STEM AUGERS
WATER LEVEL AND DATE 10.0' - 6/24/83 START 6/24/83 FINISH 6/24/83 LOGGER B.N. ZVIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-6"-6" (N)	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
2								
4		4.5						
6		X	SS-1	24"	5-7-9-13	SILTY CLAY, MOTTLED BROWN AND GRAY, MOIST, VERY STIFF, TRACE OF ROOTS, TRACE GRAVEL (CL-ML)		
8		6.5						
10		9.5						
12		X	SS-2	18"	7-4-4-4	SILTY CLAY, GRAY, WET, MEDIUM STIFF, WITH INTERBEDDED SILTY SAND AND SANDY SILT (CL-ML)		WATER AT 10' NOTED WHILE DRILLING WITH HOLLOW STEM AUGERS
14		11.5						
16		X	SS-3	17"	5-6-7-9	CLAYEY SILT, GRAY, WET, STIFF, TRACE SAND (ML)		
18		16.5						
20		19.5						
22		X	SS-4	16"	6-6-6-8	SAND, FINE TO COARSE, GRAY, WET, MEDIUM DENSE, SOME FINE GRAVEL (SW)		HARDER DRILLING BELOW 22'
24		21.5						
26		X	SS-5	0"	12-15-19-19			
28		26.5						

PROJECT NUMBER W65230.C3	BORING NUMBER ECC-5A	SHEET 2 OF 2
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTHWEST
ELEVATION 887.28 DRILLING CONTRACTOR MATECO DRILLING CO.
DRILLING METHOD AND EQUIPMENT CME 550 RIG, 3 3/4" I.D. HOLLOW STEM AUGER
WATER LEVEL AND DATE _____ START 6/24/83 FINISH 6/24/83 LOGGER B.N. ZUIBLEMAN

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	6"-6"-6" (N)	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
	30	29.5				SAND, FINE TO COARSE, GRAY, WET, VERY DENSE, GRADES TO FINE SILTY SAND (SW-SM)		
	32	31.5	SS-6	22"	13-20-27-30			
						BOTTOM OF BORING AT 31.5' ↗		



PROJECT NUMBER <u>W65230.C3</u>	BORING NUMBER <u>ECC-6A</u>	SHEET <u>1</u> OF <u>1</u>
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION NORTHEAST
ELEVATION _____ DRILLING CONTRACTOR ATEC, ASSOC.
DRILLING METHOD AND EQUIPMENT 3/4" I.D. HSA'S TO 28.5' 1/4" I.D. HSA'S TO 23.0'
WATER LEVEL AND DATE 8.5' - 09:25 HRS 9/1/83 START 0815-9/1/83 FINISH 1735-9/1/83 LOGGER J. H. JOHNSON

ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION	SYMBOLIC LOG	COMMENTS
		INTERVAL	TYPE AND NUMBER	RECOVERY	6"-6"-6" (N)	NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL		DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
								START 0815 HRS STARTED SAMPLING AT 5' BELOW GROUND SURFACE
	5.0	X	SS-1 18"		2-4-6	CLAYEY SILT, MOTTLED BROWN, MOIST, STIFF, 10% FINE SAND (ML-CL)	X	
		X	SS-2 18"		8-11-12		X	
		X	SS-3 18"		5-6-8		X	
	10.0	X	SS-4 18"		4-5-7	SILTY CLAY, GRAY, MOIST, STIFF, 10% FINE TO MED. SAND (CL)	X	
		X	SS-5 12"		4-5-8		X	
		X	SS-6 18"		10-11-11		X	Water Noted at 13.5' ON SS-6 (09:20 HRS)
	15		SS-7 18"		2-2-2	SAND, FINE TO COARSE, GRAY, WET, MED. DENSE TO DENSE, ~10% FINE GRAVEL, (SP)		Water Noted at 8.5' ON AW-RODS (09:25 HRS)
			SS-8 18"		7-7-10			
			SS-9 18"		8-22-48			
	20		SS-10 6"		9-15-20			
	23.5							
			SS-11 18"		15-27-21			
	25					SILTY CLAY, GRAY, MOIST, HARD, 10% SAND, (CL-ML)		
	28.5							
			SS-12 12"		23-50-13			NO FIRM READINGS ABOVE BACKGROUND
	30					BOTTOM OF BORING		




PROJECT NUMBER W65230.C3	BORING NUMBER ECC-7A	SHEET 1 OF 1
SOIL BORING LOG		

PROJECT ECC REMEDIAL INVESTIGATION LOCATION SOUTH OF ECC-4
ELEVATION _____ DRILLING CONTRACTOR ATEC, ASSOC.
DRILLING METHOD AND EQUIPMENT 3 1/4 HSA'S TO 29.5 FT. BELOW GROUND SURFACE
WATER LEVEL AND DATE 12.5 FT - 9/1/83 START 9/1/83-1630 FINISH 9/1/83-1810hrs LOGGER I. H. JOHNSON


ELEVATION	DEPTH BELOW SURFACE	SAMPLE			STANDARD PENETRATION TEST RESULTS 6"-6"-6" (N)	SOIL DESCRIPTION NAME, GRADATION OR PLASTICITY, PARTICLE SIZE DISTRIBUTION, COLOR, MOISTURE CONTENT, RELATIVE DENSITY OR CONSISTENCY, SOIL STRUCTURE, MINERALOGY, USCS GROUP SYMBOL	SYMBOLIC LOG	COMMENTS DEPTH OF CASING, DRILLING RATE, DRILLING FLUID LOSS, TESTS AND INSTRUMENTATION
		INTERVAL	TYPE AND NUMBER	RECOVERY				
						FILL, SAND, SILT, CLAY, MOTTLED BROWN, SOME TRASH		DRILLED TO 5.0 FT TO START SPLIT-SPoon SAMPLING
						4.0'		
5		X	SS-1 10"		2-5-9	SILTY CLAY, MOTTLED GREEN, MOIST, STIFF, (CL)		
		X	SS-2 12"		10-13-14	CLAYEY SILT, GRAY, MOIST, STIFF, STIFF TO HARD, (CL-ML)		
		X	SS-3 12"		13-16-21			
10		X	SS-4 9"		16-19-20			
		X	SS-5 11"		17-30-28	12.0'		
		X	SS-6 16"		12-17-18	SILTY SAND, FINE, GRAY, WET, DENSE, (SM)		
		X	SS-7 18"		11-20-27	13.0'		
15		X	SS-8 18"		18-19-35	CLAYEY SILT, GRAY, MOIST, HARD, WITH INTERBEDDED, SILTY SAND, FINE, GRAY, MOIST TO WET, DENSE (ML-CL) AND (SM)		WATER NOTED AT 15.5' ON RODS
		X	SS-9 18"		4-28-46			
		X	SS-10 14"		20-29-21			
20								
		X	SS-11 18"		17-30-39	CLAYEY SILT, GRAY, MOIST, HARD, -10 TO 15% SAND, (ML-CL)		
25								NO HNU READINGS ABOVE BACKGROUND
		X	SS-12 9"		49-65 1/6"	SILTY SAND, FINE, GRAY, WET, (SM)		
30						BOTTOM OF BORING AT 29.5'		WATER AT 12.5 FT. AT COMPLETION

APPENDIX C
MONITORING WELL CONSTRUCTION DETAILS




NOTE: Figure not drawn to scale

FIGURE B-1
MONITORING WELL CONSTRUCTION
 ECC-1 CLUSTER
 TM 3-1




NOTE: Figure not drawn to scale

FIGURE B-2
MONITORING WELL CONSTRUCTION
 ECC-2 CLUSTER
 TM 3-1




NOTE: Figure not drawn to scale

FIGURE B-3
MONITORING WELL CONSTRUCTION
 ECC-3 CLUSTER
 TM 3-1




NOTE: Figure not drawn to scale

FIGURE B-4
MONITORING WELL CONSTRUCTION
 ECC-4 CLUSTER
 TM 3-1




NOTE: Figure not drawn to scale

FIGURE B-5
MONITORING WELL CONSTRUCTION
 ECC-5A
 TM 3-1



NOTE: Figure not to scale.

FIGURE B-6
MONITORING WELL CONSTRUCTION
ECC - 6A AND ECC - 7A
 ECC SITE
 TM 3-1



NOTE: 2", 4" and 6" galvanized nipples used to connect K - Packers and check valve.

FIGURE B-7
TYPICAL FLOWING WELL PACKER
SYSTEM INSTALLATION
 ECC SITE
 TM 3-1

APPENDIX D
LABORATORY SOIL CLASSIFICATION TEST RESULTS

LABORATORY TESTING PROCEDURES

Grain Size Tests

Grain size tests were performed to determine the particle size and distribution of the samples tested. The grain size distribution of soils coarser than a No. 200 sieve was determined by passing the sample through a standard set of nested sieves. These tests are similar to those described by ASTM D-421 and D-422. The results are presented on the attached Grain Size Distribution Sheets.

Moisture Content

The moisture content is the ratio expressed as a percentage of the weight of water in a given mass of soil to the weight of the solid particles. This test was conducted in accordance with ASTM Designation D-2216-66. The results of these tests are presented on the attached Summary of Laboratory Test Data.

Specific Gravity of Soil Solids

The specific gravity of soil solids is the ratio of the weight in air of a given volume of soil particles to the weight in air of an equal volume of water. This test was conducted on selected soil samples in accordance with ASTM designation D-854-58. The results of these tests are presented on the attached Summary of Laboratory Data.

Atterberg Limits Testing

Representative samples of the soils were selected for Atterberg Limits testing to determine the soil plasticity characteristics. The soil's Plastic Index (PI) is representative of this characteristic and is bracketed by the Liquid Limit (LL) and the Plastic Limit (PL). The LL is the moisture content at which the soil will flow as a heavy viscous fluid and is determined in accordance with ASTM D-423. The PL is the moisture content at which the soil begins to lose its plasticity and is determined in accordance with ASTM D-424. The data obtained are presented on the attached Summary of Laboratory Test Data and boring logs.

BORING LOG TERMINOLOGY

- Permit Number: This mineral Well Permit Number is assigned to Materials Testing Consultants, by the State of Michigan Department of Natural Resources Geological Survey Division. Materials Testing Consultants is obligated under the rules of the Mineral Well Act to plug test borings in a specified manner.
- Sample Type: "SBS" and "L" are the split barrel and liner samplers used to recover soil samples in the ASTM D 1586 Standard Penetration Test.
- "S.T." refers to the thin-walled sampler (Shelby Tube) used to recover relatively undisturbed soil samples in the ASTM D 1587 method of sampling.
- "A" refers to a disturbed auger sample.
- "C" refers to a rock core sample obtained by Diamond Core Drilling in accordance with ASTM D 2113.
- Boring Method: "H.S.A." refer to the Hollow Stem Auger.
- "S.S.A." refers to the Solid Stem Auger.
- "W" refers to the Wash Boring Method.
- "R" refers to the Rotary Method.
- "C" refers to the Casing Method.
- Water Observations: Depth of water is measured from the top of ground to top of water level. Initial depth indicates water encountered during boring, completion depth indicates water level immediately after boring, and depth after "X" number hours indicates water level after a time period.
- Water observations in pervious soils are considered reliable groundwater levels for that date. Water observations in impervious soils may not be accurate groundwater measurements unless records are made over several days' time. The groundwater level will fluctuate for both pervious and impervious soils.
- Soils Description: Visual classification of major soil constituents.

II

Color: When the color of the soil is uniform throughout, a single color such as brown, gray or black will be used, modified by adjective such as light and dark. If the soil's predominant color is shaded by a secondary color, the secondary color precedes the primary color, such as: gray-brown, yellow-brown. If two major and distinct colors are swirled throughout the soil, the colors will be described by the term mottled, such as: Mottled brown and gray.

Size:	<u>Soil Components</u>	<u>Size</u>
	Boulders	Larger than 8"
	Cobbles	8" to 3"
	Gravel--Coarse	3" to 3/4"
	--Fine	2 mm. to 3/4"
	Sand --Coarse	2 mm. to 0.6 mm.
	--Medium	0.6 mm.-0.2 mm.
	--Fine	0.2 mm.-0.06 mm.
	Silt	0.06 mm.-0.002 mm.
	Clay	0.002 mm and smaller

Minor Component Quantifying Term:	Trace 1-10%	(Percentages are estimates unless a sieve analysis is performed)
	Little 10-20%	
	Some 20-35%	
	And 35-50%	

Layer or Stratum: Soil mass which can be characterized, for engineering purposes, by a single set of strength and classification parameters.

Lenses: Lenses of soil occur within a soil layer and range in thickness from a fraction of an inch to approximately one (1) foot thick.

Seams: Planer opening in a soil layer filled with soils of different characteristics. Soil seams are usually a fraction of an inch thick and may occur in various directions.

III

Density: Granular Soils (Cohesionless)

<u>Number of Blows</u>	<u>Relative Density</u>	<u>Compactness</u>
0-4	0-20%	Very Loose
5-10	20-40%	Loose
11-30	40-70%	Medium Dense
31-50	70-90%	Dense
above 50	90-100%	Very Dense

Consistency: Cohesive Soils

<u>Number of Blows</u>	<u>Approximate Shear Strength in K.S.F.</u>	<u>Cohesion</u>
0-2	0.25	Very Soft
3-4	0.25-0.5	Soft
5-8	0.5-1	Medium Stiff
9-16	1-2	Stiff
17-32	2-4	Very Stiff
above 32	above 4	Hard

Grading: When Soil characteristics vary gradually with depth within the same soil stratum, the variation is described by using the term "grading".

N.P.M.: Natural Percent Moisture of in situ soil sample.

N.D.: Natural Density of in situ soil sample in p.c.f.

S.S.: Shear Stength of cohesive soil samples as determined by the Unconfined Compression Tests in K.S.F.

Classification Data:

Laboratory data to assist in classification of soils and classification of soil characteristics. ie: Plastic Limit, Liquid Limit.




MATERIALS TESTING CONSULTANTS INC.

UNIFIED SOIL CLASSIFICATION SYSTEM

MAJOR DIVISIONS			LETTER SYMBOL	TYPICAL DESCRIPTIONS
COARSE GRAINED SOILS MORE THAN 50% OF MATERIAL IS <u>LARGER</u> THAN NO. 200 SIEVE SIZE	GRAVEL AND GRAVELLY SOILS MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE	CLEAN GRAVELS (LITTLE OR NO FINES)	GW	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
			GP	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
		GRAVELS WITH FINES (APPRECIABLE AMT. OF FINES)	GM	SILTY GRAVELS, GRAVEL-SANDY-SILT MIXTURES
			GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES
	SAND AND SANDY SOILS MORE THAN 50% OF COARSE FRACTION PASSING NO. 4 SIEVE	CLEAN SAND (LITTLE OR NO FINES)	SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
			SP	POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
		SANDS WITH FINES (APPRECIABLE AMT. OF FINES)	SM	SILTY SANDS, SAND-SILT MIXTURES
			SC	CLAYEY SANDS, SAND-CLAY MIXTURES
FINE GRAINED SOILS MORE THAN 50% OF MATERIAL IS <u>SMALLER</u> THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT <u>LESS</u> THAN 50	ML	INORGANIC SILTS & VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
		OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	
	SILTS AND CLAYS LIQUID LIMIT <u>GREATER</u> THAN 50	MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS	
		CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS	
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
	HIGHLY ORGANIC SOILS	PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS	

PLASTICITY CHART

FOR LABORATORY CLASSIFICATION OF FINE GRAINED SOILS



SUMMARY OF LABORATORY TEST DATA

Boring Number	Sample Depth	Sample Type**	Sample Description and USCS Classification	Unit Weight pcf		Unconfined Compressive Strength KSF	Percent Finer No. 200 Sieve	Specific Gravity	Natural Moisture Content	Atterberg Limits			MTCI Sample Number	
				Wet	Dry					L.L.	P.L.	P.I.		
1A	2-4'	SS 2	gray silty clay (CL)						11.4	20.9	13.5	7.4	92921	
1A	4-6'	SS 3	gray clay with f-c sand and f gravel (CL)				58.8	2.68					92899	*
1A	14-16'	SS 8	gray silty clay (CL-ML)						9.4	16.9	11.4	5.5	92922	
1A	18-20'	SS 10	gray silty clay (CL-ML)						5.3	15.0	10.8	4.2	92923	
1A	28-30'	SS 12	brown & gray mottled silty clay (CL-ML)						7.0	18.0	12.5	5.5	92924	
1A	34½-36'	SS 13	gray clay with f to c sand and f gravel (CL)				56.6	2.68					92900	*
1C	23½-25'	SS 1	gray fine to c sand with some f gravel (SW)				6.0						92901	*
1C	29½-31'	SS 2	gray fine sand with some silt (SM)				34.6	2.670					92902	*
1C	34½-36'	SS 3	gray silty clay with f-c sand & f gravel (CL-ML)						5.7	22.6	18.3	4.3	92925	
1C	39½-41'	SS 4	gray clay with f-c sand & f gravel (CL)				65.5	2.70					92903	*

* Graphic Presentations of Results of Triaxial, Consolidation, CBR, Proctor, Grain Size, and other tests follow this summary

** SS = Solist Spoon Sample (ASTM D 1586)
UD = Undisturbed Sample (ASTM D 1587)

Materials Testing Consultants, Inc.
593 PLYMOUTH N.E., GRAND RAPIDS, MICH. 49503 • PHONE 616/460-9400

JOB NUMBER: 162G

PAGE 1 OF 6

SUMMARY OF LABORATORY TEST DATA

Boring Number	Sample Depth	Sample Type**	Sample Description and USCS Classification	Unit Weight pcf		Unconfined Compressive Strength KSF	Percent Finer No. 200 Sieve	Specific Gravity	Natural Moisture Content	Atterberg Limits			MTCI Sample Number	
				Wet	Dry					L.L.	P.L.	P.I.		
1C	54½-56'	SS 7	brown & gray mottled clay (CL)						10.5	40.8	21.9	18.9	92926	
1C	64½-65½'	SS 10	gray silty clay with some f-c sand (CL)						5.9	16.2	11.8	4.4	92927	
1C	74½-76'	SS 12	brown silt with f-c sand & f gravel (ML)				58.3	2.68					92904	*
1C	79½-80½'	SS 13	brown silt with f-c sand and f gravel (ML)						6.0	15.6	11.9	3.7	92928	
1C	139½-141'	SS 25	blue gray silty clay (CL)						15.2	47.5	19.4	28.1	92929	
1C	154½-156'	SS 28	gray silty f-c sand with some f gravel (SM-SW)				11.5						92905	*
2C	4-6'	SS 3	gray silty clay with some fine gravel (CL-ML)						7.5	17.7	11.3	6.4	92930	
2C	12-14'	SS 7	gray silty clay (CL-ML)						7.8	16.3	10.9	5.4	92931	
2C	16-18'	SS 9	gray f-c sand (SP)				5.8						92906	*
2C	20-22'	SS 11	gray f-c sand with some fine gravel (SW)				4.9						92907	*

* Graphic Presentations of Results of Triaxial, Consolidation, CBR, Proctor, Grain Size, and other tests follow this summary

** SS = Split Spoon Sample (ASTM D 1586)
UD = Undisturbed Sample (ASTM D 1587)

Materials Testing Consultants, Inc.
693 PLYMOUTH N.E., GRAND RAPIDS, MICH. 49506 • PHONE 616/456-6469

JOB NUMBER: 162G

PAGE 2 OF 6

SUMMARY OF LABORATORY TEST DATA

Boring Number	Sample Depth	Sample Type**	Sample Description and USCS Classification	Unit Weight pcf		Unconfined Compressive Strength KSF	Percent Finer No. 200 Sieve	Specific Gravity	Natural Moisture Content	Atterberg Limits			MTCI Sample Number	
				Wet	Dry					L.L.	P.L.	P.I.		
2C	26-28'	SS 14	gray f-c sand with some f gravel (SW)				2.3						92965	*
2C	32-34'	SS 17	gray f-c sand with some silt (SM)				33.9						92908	*
2C	44½-46'	SS 20	gray clay with some f-c sand (CL)						2.9	23.9	12.5	11.4	92932	
2C	49½-51'	SS 21	gray clay with some f-c sand (CL)				67.6	2.699					92909	*
2C	79½-80½'	SS 27	gray clayey silt (CL-ML)						8.0	19.5	13.1	6.4	92933	
2C	99½-100½'	SS 31	brown f-c sand with little gravel (SP-SM)				10.0						92910	*
2C	119½-121'	SS 35	gray silty clay (CL)						10.5	22.2	14.7	7.5	92934	
2C	144½-146'	SS 40	gray clay with some f-c sand (ML-CL)						15.8	21.1	14.3	6.8	92935	
2C	149½-151'	SS 41	gray f-m sand with limestone (SM) chips & little silt				13.9						92911	*
3A	2-4'	SS 2	brown clay fill (CL)						12.7	26.4	16.5	9.9	92936	

* Graphic Presentations of Results of Triaxial, Consolidation, CBR, Proctor, Grain Size, and other tests follow this summary

** SS = Split Spoon Sample (ASTM D 1586)
UD = Undisturbed Sample (ASTM D 1587)

Materials Testing Consultants, Inc.
693 PLYMOUTH N.E., GRAND RAPIDS, MICH. 49505 • PHONE 516/456-8469

JOB NUMBER: 162G

PAGE 3 OF 6

SUMMARY OF LABORATORY TEST DATA

Boring Number	Sample Depth	Sample Type**	Sample Description and USCS Classification	Unit Weight pcf		Unconfined Compressive Strength KSF	Percent Finer No. 200 Sieve	Specific Gravity	Natural Moisture Content	Atterberg Limits			MFCI Sample Number	
				Wet	Dry					L.L.	P.L.	P.I.		
3A	8-10'	SS 5	brown f-c sand with little silt (SM-SW)				11.1						92912	*
3A	14-16'	SS 8	brown f-c sand with little f-c gravel & silt (SM)				15.4						92913	*
3A	18-20'	SS 10	gray silty clay with little f-c sand (CL-ML)						9.9	17.6	13.1	4.5	92937	
3C	34½-36'	SS 14	gray silty clay (CL-ML)						10.6	21.1	14.2	6.9	92938	
3C	64½-66'	SS 20	gray silty clay with some f-c sand & f gravel (CL-ML)						7.3	19.8	14.3	5.5	92939	
3C	104½-106'	SS 28	gray clayey silt with trace sand (ML)						8.7	17.0	13.6	3.4	92940	
3C	129½-131'	SS 33	brown silty clay (CL)						13.7	35.1	19.9	17.2	92941	
3C	139½-141'	SS 35	gray f-m sand with little silt (SM)				12.9						92914	*
4C	6-8'	SS 4	gray clayey silt with little f-c sand (ML)						11.4	16.5	12.6	3.9	93000	
4C	8-10'	SS 5	gray f-c sand with clay (SC)				47.8	2.702	10.1				93001	*

* Graphic Presentations of Results of Triaxial, Consolidation, CBR, Proctor, Grain Size, and other tests follow this summary

** SS = Split Spoon Sample (ASTM D 1586)
UD = Undisturbed Sample (ASTM D 1587)

Materials Testing Consultants, Inc.
855 PLYMOUTH N.E., GRAND RAPIDS, MICH. 49508 • PHONE 616/456-5458

JOB NUMBER: 162G

PAGE 4 OF 6

SUMMARY OF LABORATORY TEST DATA

Boring Number	Sample Depth	Sample Type**	Sample Description and USCS Classification	Unit Weight pcf		Unconfined Compressive Strength KSF	Percent Finer No. 200 Sieve	Specific Gravity	Natural Moisture Content	Atterberg Limits			MTCI Sample Number	
				Wet	Dry					L.L.	P.L.	P.I.		
4C	12-14'	SS 7	gray f-c sand with clay (SC)				39.4	2.728	4.8				93002	*
4C	18-19'	SS 10	gray silty clay (CL)						7.6	19.1	11.9	7.2	93003	
4C	20-22'	SS 11	gray clay with f-c sand (CL)				53.0	2.734	3.1				93004	*
4C	39½-41'	SS 16	gray clay with f-c sand (CL)						9.9	21.8	12.8	9.0	93005	
4C	54½-56'	SS 19	greenish gray clay (CL).						19.9	38.0	17.6	10.4	93006	
4C	94½-95.9'	SS 27	gray clayey silt (ML)						9.4	18.2	14.6	3.6	92942	
4C	139½-141'	SS 36	brown silty clay with f-c sand (CL)						8.2	37.6	16.1	21.5	92943	
4C	149½-150.9'	SS 38	gray fine sand with little silt (SM)				13.1						92915	*
4C	154½-155½'	SS 39	gray f-c sand with little silt (SM)				12.7						92916	*
5A	4½-6½'	SS 1	brown & gray mottled silty clay w/tr gravel (CL-ML)						7.8	19.4	14.2	5.2	92944	

* Graphic Presentations of Results of Triaxial, Consolidation, CBR, Proctor, Grain Size, and other tests follow this summary

** SS = Split Spoon Sample (ASTM D 1586)
UD = Undisturbed Sample (ASTM D 1587)

Materials Testing Consultants, Inc.
693 PLYMOUTH N.E., GRAND RAPIDS, MICH. 49506 • PHONE 816/456-2469

JOB NUMBER: 162G

PAGE 5 OF 6

SUMMARY OF LABORATORY TEST DATA

Boring Number	Sample Depth	Sample Type**	Sample Description and USCS Classification	Unit Weight pcf		Unconfined Compressive Strength KSF	Percent Finer No. 200 Sieve	Specific Gravity	Natural Moisture Content	Atterberg Limits			MTCI Sample Number	
				Wet	Dry					L.L.	P.L.	P.I.		
5A	9½-11½'	SS 2	gray f-c sand with silt (SM)				43.6	2.716					92917	*
5A	19½-20½'	SS 4	gray f-c sand with little f gravel (SW)				2.8						92918	*
5A	29½-31½'	SS 6	gray f-c sand with trace gravel and silt (SW)				5.9						92919	*
5A	29½-31½'	SS 7	gray fine sand with some silt (SM)				26.7						92920	*

* Graphic Presentations of Results of Triaxial, Consolidation, CBR, Proctor, Grain Size, and other tests follow this summary

** SS = Split Spoon Sample (ASTM D 1586)
UD = Undisturbed Sample (ASTM D 1587)

Materials Testing Consultants, Inc.
602 PLYMOUTH N.E., GRAND RAPIDS, MICH. 49503 • PHONE 616/456-5466


JOB NUMBER: 162G

PAGE 6 OF 6

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 1A SAMPLE NUMBER 92899




BOREING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI	
B 1A	4-6'	CL gray clay w/f-c sand and f. gravel					

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 1A SAMPLE NUMBER 92900




BORING	DEPTH	GRAVEL					SAND			SILT OR CLAY
		COARSE	FINE	COARSE	MEDIUM	FINE				
B 1A	34.5-36'	CL	gray clay w/f-c sand and f gravel							

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/11/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 1C SAMPLE NUMBER 92901



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	


BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI	
B 1C	23-1/2 to 25'	SW gray f-c sand w/some f gravel					

TECHNICIAN IH & GT COMPUTED BY IH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 1C SAMPLE NUMBER 92902



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI
B 1C	29 1/2 - 31'	SM gray fine sand w/some silt				

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS


REMARKS

Materials Testing Consultants

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Michigan
 JOB NUMBER 162G BORING NUMBER B 1C SAMPLE NUMBER 92903



PROJECT Zionsville, Indiana

DATE 7/25/83

SAMPLE NUMBER 92904



BORING	DEPTH	CLASSIFICATION		NAT. WC	LL	PL	PI
B 1C	74½-76'	ML	brown silt w/f-c sand & f gravel				

LH CHECKED BY JNS


REMARKS

Charles T. Young

GRADATION CURVE

DATE 7/8/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 1C SAMPLE NUMBER 92905



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI
B 1C	154 1/2 - 156'	SM-SW gray silty f-c sand w/ some f gravel				

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS


PERCENT FINER BY WEIGHT

GRAIN SIZE IN MILLIMETERS

DATE 7/8/83

PROJECT Zionsville, Indiana

SAMPLE NUMBER 92906



JNS

REMARKS

GRADATION CURVE

DATE 7/11/83


CLIENT CH2M HILL

PROJECT Zionsville, Indiana

JOB NUMBER 162G

BORING NUMBER B 2C

SAMPLE NUMBER 92907



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION		NAT. WC	LL	PL	PI
B 2C	20-22'	Sw	gray f-c sand w/some fine gravel				

TECHNICIAN LH & GT
COMPUTED BY LH
CHECKED BY JNS

REMARKS




Materials Testing Systems, Inc.

GRADATION CURVE

DATE 7/11/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 2C SAMPLE NUMBER 92965



BORING	DEPTH	GRAVEL			SAND			SILT OR CLAY
		COBBLES	COARSE	FINE	COARSE	MEDIUM	FINE	
B 2C	26-28'							


BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI
B 2C	26-28'	SW gray f-c sand with some f gravel				

TECHNICIAN LH & GT COMPUTED BY LH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/5/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 2C SAMPLE NUMBER 92908



COBBLES		GRAVEL		SAND			SILT OR CLAY		
		COARSE	FINE	COARSE	MEDIUM	FINE			
BORING	DEPTH	CLASSIFICATION			NAT. WC	LL	PL	PI	
B 2C	32-34'	SM	gray f-c sand with some silt						


TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS
 REMARKS

MADE BY Testing Company

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 2C SAMPLE NUMBER 92909



BORING	DEPTH	GRAVEL				SAND				SILT OR CLAY			
		COARSE	FINE	COARSE	FINE	COARSE	MEDIUM	FINE	NAT. WC	LL	PL	PI	
B 2C	49 1/2' - 51'	CL	gray clay with some f-c sand										

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS

REMARKS




Materials Testing Consultants, Inc.

GRADATION CURVE

DATE 7/11/83


CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 2C SAMPLE NUMBER 92910



GRADATION CURVE

DATE 7/5/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 2C SAMPLE NUMBER 92911



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI
B 2C	149 1/2 - 151'	SM gray f-m sand w/limestone chips & little silt				

TECHNICIAN IH COMPUTED BY IH CHECKED BY JNS
 REMARKS


March Testing Company

GRADATION CURVE

DATE 7/7/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana

JOB NUMBER 162G BORING NUMBER B 3A SAMPLE NUMBER 92912



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI	
B 3A	8-10'	SM-SW brown f-c sand with little silt					

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS


REMARKS

CH2M HILL

GRADATION CURVE

DATE 7/8/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 3A SAMPLE NUMBER 92913



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI	
B 3A	14-16'	SM brown f-c sand w/little f-c gravel & silt					


TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS

REMARKS

GRADATION CURVE

DATE 7/7/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 3C SAMPLE NUMBER 92914



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI
B 3C	139.5 to 141'	SM gray f-m sand with little silt				


TECHNICIAN LH & GT
 COMPLETED BY LH
 CHECKED BY JNS

Materials Testing Corporation

GRADATION CURVE

DATE 7/13/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 4C SAMPLE NUMBER 93001



COBBLES	GRAVEL		SAND			SILT OR CLAY		
	COARSE	FINE	COARSE	MEDIUM	FINE			
BORING	DEPTH	CLASSIFICATION		NAT. WC	LL	PL	PI	
B 4C	8 - 10'	SC	gray f-c sand w/ clay					

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS


REMARKS

DATE 7/25/83

PROJECT Zionsville, Indiana

BORING NUMBER B 4C

SAMPLE NUMBER 93002




TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 4C SAMPLE NUMBER 93004



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	


BORING	DEPTH	CLASSIFICATION		NAT. WC	LL	PL	PI
B 4C	20-22'	CL	gray clay w/f-c sand				

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/11/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 4C SAMPLE NUMBER 92915



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	


BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI	
B 4C	149.5 - 150.9'	SM gray f sand w/ little silt					

TECHNICIAN IH & GT COMPUTED BY IH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/11/83

CLIENT CH2M HILL PROJECT Zionsville, Michigan
 JOB NUMBER 162G BORING NUMBER B 4C SAMPLE NUMBER 92916



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	


BORING	DEPTH	CLASSIFICATION		NAT. WC	LL	PL	PI
B 4C	154.5 to 155.5	SM	gray f-c sand w/little silt				

TECHNICIAN LH & GT COMPUTED BY LH CHECKED BY JNS
 REMARKS

GRADATION CURVE

DATE 7/25/83


CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 5A SAMPLE NUMBER 92917



GRADATION CURVE

DATE 7/8/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 5A SAMPLE NUMBER 92918




COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION	NAT. WC	LL	PL	PI	
B 5A	19.5-21.5'	SW gray f-c sand w/ little fine gravel					

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS
 REMARKS

DATE 7/8/83

ATE 7/8/83
92919




52

PERCENT FINER BY WEIGHT

GRADATION CURVE

DATE 7/25/83

CLIENT CH2M HILL PROJECT Zionsville, Indiana
 JOB NUMBER 162G BORING NUMBER B 5A SAMPLE NUMBER 92920



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

BORING	DEPTH	CLASSIFICATION		NAT. WC	LL	PL	PI	
B 5A	29½'-31½'	SM	gray fine sand with some silt					

TECHNICIAN LH COMPUTED BY LH CHECKED BY JNS
 REMARKS _____